

SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyrighted, 1889, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXL.—No. 7.
ESTABLISHED 1845.

NEW YORK, AUGUST 17, 1889.

\$3.00 A YEAR.
WEEKLY.



THE NEW CROTON AQUEDUCT WORKS—THE GREAT DAM AT SODOM.—[See page 108.]

Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN.

A. E. BEACH.

TERMS FOR THE SCIENTIFIC AMERICAN.

One copy, one year, for the U. S. or Canada. \$3 00
 One copy, six months, for the U. S. or Canada. 1 50
 One copy, one year, to any foreign country belonging to Postal Union, 4 00
 Remit by postal or express money order.

Australia and New Zealand.—Those who desire to receive the SCIENTIFIC AMERICAN, for a little over one year, may remit \$1 in current Colonial bank notes. Address

MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

The Scientific American Supplement

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$5.00 a year, for U. S. and Canada. \$6.00 a year to foreign countries belonging to the Postal Union. Single copies, 10 cents. Sold by all newsdealers throughout the country.

Combined Rates.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to any address in U. S. or Canada, on receipt of seven dollars.

The safest way to remit is by draft, postal order, express money order, or registered letter.

Australia and New Zealand.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for a little over one year on receipt of £2 current Colonial bank notes.

Address MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

NEW YORK, SATURDAY, AUGUST 17, 1889.

Contents.

(Illustrated articles are marked with an asterisk.)

Bath, aqua ammonia.....	104	Machine, electric, water spray.....	100
Boats, torpedo, hot decks.....	102	Machinery, woodworking.....	97
Books and publications.....	103	Material, joint-making, new.....	92
Buckle, locking, Blum's.....	105	Method, Pasteur's, criticism.....	105
Business and personal.....	101	Museum, Boulak, Cario.....	105
Cases, patent, important.....	101	Non-conductor, fireproof, new.....	104
Catalogue, American.....	102	Notes and queries.....	106
Coco de mer.....	105	Notes, natural history.....	102
Coupling, car, Chicago.....	103	Notes, of food products.....	102
Dam and reservoir, Sodom.....	103	Rabies, Pasteur's method.....	102
Dam, Sodom, details.....	103	Rails or bars, manuf. of.....	102
Dentistry, operative.....	101	Reservoirs, Croton, map of.....	103
Electricity, work of.....	101	Reservoirs, New York water sup- ply.....	97
Exhibition, Paris.....	97	Silk, artificial.....	101
Experiment, search light, recent.....	98	Silk, umbrella, Haight's.....	101
Failure, hearth, Angouleme.....	104	Streams, utilizing running.....	97
Flames, radiating power of.....	101	Trials, speed, British squadron.....	97
Hotter in Utah than in Siberia.....	104	Troubles, lung, relief for.....	101
Inventions, agricultural.....	106	Vegetables, medicinal properties.....	98
Inventions, electrical.....	106	Warning for bathing season.....	100
Inventions, index of.....	107	Water, how and when to drink.....	105
Inventions, miscellaneous.....	103	Water supply, New York, inade- quate.....	96
Iron, crude, converting.....	99	Waves, sea, height.....	104
Leverrier, statue of.....	99, 100		

TABLE OF CONTENTS OF SCIENTIFIC AMERICAN SUPPLEMENT No. 711.

For the Week Ending August 17, 1889.

Price 10 cents. For sale by all newsdealers.

I. AGRICULTURE.—How to Raise Turkeys.—A collection of hints and suggestions on the raising of the delicate fowls, so often the cause of trouble to farmers.....	11364
Pearl Duchesse d'Angouleme.—The recent famous pear tree, with hints as to its culture and general treatment.....	11362
II. BIOLOGY.—Development of the Embryo.—A note of some interesting biological researches.—By Prof. PREYER, of Berlin.....	11365
The "Hatchery" of the Sun Fish.—A curious incident in the life history of the common sunfish.—1 illustration.....	11363
III. CHEMISTRY.—On Allotropic Forms of Silver.—By M. CAREY LEA.—A continuation of this paper, containing one of the most important researches in the history of silver, with statement of interesting results attained.....	11361
On the Occurrence of Paraffine in Crude Petroleum.—A valuable contribution to the history of paraffine, with reference to petroleum and osokerite.....	11361
Turpentine and its Products.—By EDWARD DAVIES.—A resume of the work done by chemists in the turpentine products.—The different compounds produced therefrom.....	11361
IV. ELECTRICITY.—Electric Lighting at the Paris Exhibition.—The Oerlikon works.—A very exhaustive exhibition of electric apparatus described and illustrated.—12 illustrations.....	11356
Magnetism in relation to Induced Electromotive Force and Current.—By WILHELM THOMSON.—A most impressive paper, bringing the obscure laws of magnetic induction within the understanding of all without the application of mathematics.—12 illustrations.....	11354
The Ader Flourish of Trumpets.—One of the curiosities in telephony from the Paris exhibition, by which sounds are transmitted to a large audience.....	11358
The Electric Motor Tests on the New York Elevated Railroad.—Abstracts of tests which were recently made of the Daft motor on the elevated railroad of this city.....	11353
V. ETHNOLOGY.—Ancient Lake Dwellings.—Interesting abstract of what is known about lake dwellings, the history of their construction, and the "finds" made on the sites by archaeologists.....	11363
VI. FORESTRY.—Succession of Forest Growths.—A valuable paper on forestry, treating of the evils done by man and a plea for the necessity of intelligent treatment of our woods.....	11362
VII. HYGIENE AND MEDICINE.—Acetic Acid as a Disinfectant.—Use of acetic acid in septic medical cases as a substitute for carbolic acid and bichloride of mercury.....	11365
Counter-irritation in Whooping Cough.—By G. F. INGLOT, M.D.—Application of irritants to the skin for curing the paroxysms of whooping cough.....	11365
On the Health Value to Man of the So-called Divinely Beneficent Gift, Tobacco.—By J. M. W. KITCHEN, M.D.—The evils to man and to the soil.—A formidable series of accusations well expressed.....	11365
Water as a Therapeutical Agent.—By F. C. ROBINSON, M.D.—An interesting resume of different applications of water in therapeutics.—Suggestions of use for all households.....	11364
VIII. MILITARY ENGINEERING.—Gibraltar.—A history of this important strategic position and of the different sieges the fortress has undergone.....	11352
Gibraltar and Neighborhood.—A consular report on the statistics of the famous military station.....	11352
The Defense of Gibraltar.—Experimental Naval and Military Operations.—Interesting series of operations recently carried out under the shadow of the historic rock.—1 illustration.....	11352
IX. NAVAL ENGINEERING.—Clark's Gyroscopic Torpedoes.—A recent torpedo, in which all the possible parts are made to rotate.—2 illustrations.....	11353
The First Steamboat on the Seine.—The Marquis de Jouffroy's steamer of 1816.—1 illustration.....	11353
The Franz Josef I. New War Ship.—Details of the dimensions of the new Austrian ship.—Her armament, speed, armor, etc.....	11353
X. PHOTOGRAPHY.—Orthochromatic Photography.—By OSCAR O. LITZKOW.—The last developments in this interesting branch of photographic art, with formulae.....	11360
Platotype Printing.—A description of the most advanced method of conducting the platinum print process.....	11360
XI. PHYSICS.—Iridescent Crystals.—By LORD RAYLEIGH.—An abstract of a lecture by the distinguished physicist, detailing some interesting experiments applicable to the colored reflection observed in crystals of chloride of potash.—1 illustration.....	11366
Transmission of Pressure in Fluids.—By ALBERT B. PORTER.—An apparatus for illustrating the laws of transmission of pressure in fluids, suitable for lecture purposes.—1 illustration.....	11363
XII. TECHNOLOGY.—Notes on Dyewood Extracts and Similar Preparations.—By LOUIS BIERZOL.—The recent development in the preparation of dyewood extracts, with notes of their adulterations.....	11359

A RECENT SEARCH LIGHT EXPERIMENT.

The recent experiments with electrical search lights on the Spit, near Hurst Castle, opposite the Needles passage, in the Solent, England, were, so far as can be learned, not in anywise novel, nor is it easy to see how, as is claimed in some quarters, these lights can balk torpedo boat attack. The design was to protect the roadstead, and it is claimed that this was accomplished. It is true that the torpedo boats were discovered in the blackness and held in broad view for the fire of the shore batteries. Perhaps these batteries could have destroyed them before they reached the shipping, perhaps not. Even if so, it does not prove very much.

An account says that a great volume of smoke made by the war ships accompanying the little craft, purposely to mask their design, blew out to sea, the wind being outward, thus enabling the search lights to bring the enemy out clear. But the wind does not always blow in that direction, and hence the test would have been more satisfactory had the wind favored the attack.

Again, the best promise of the torpedo boat is thought to be in the protection of, rather than in the attack upon, harbors. Electrical search lights might or they might not advantage ships coming in from the sea. Supposing they did locate the attacking torpedo boats as they came up; unless there was the power to beat them off, of what value would the knowledge be? If the heavy quick-firing guns now being set up atop the conning towers of the new torpedo boats realize the promises made for them, the torpedo boat will have a palpable advantage, because able to throw upon a ship as heavy shot as can be thrown back, before it an immense target and a steady one, though itself affording only a small and running mark for the ship's gunners stationed aloft and along.

THE INADEQUATE SUPPLY OF WATER FOR NEW YORK.

For complete physical independence there are few undertakings that will compare favorably with the new Croton scheme. Tested by any one of several elementary methods, it departs so widely from the requirements that the results only corroborate the hypothesis that the scheme claims absolute freedom from all obligations of physical science.

Take, for instance, the relation that should exist between the capacity of the aqueducts and the available supply. So far as any advantages of storage are concerned, the surveys explain that, owing to the topography of the 361 square miles constituting the basin, there is an area of 115 square miles in the lower part of the valley that cannot be made to contribute to reservoirs except a terminal one be provided, and therefore this portion may be deducted from the whole, leaving the available area for storage 246 square miles.

Speaking generally, one square mile of watershed will supply from 13,000 to 15,000 persons, provided the allotment is only fifty gallons. Now, since New York needs one hundred gallons per capita, it is plain that one square mile of the Croton basin will only supply half this number, or from 6,500 to 7,500 persons. Estimating the population at present to be 1,700,000, the number of persons depending on each square mile of watershed (omitting the inhabitants thereof) is about 7,000. But to furnish this population with water during the present summer, it is computed that 23 thousand million gallons of storage would be necessary; and inasmuch as the storage provided amounts scarcely to 9 thousand million gallons, there is a deficiency of 14 thousand million gallons.

This volume of storage (nine thousand million gallons) is what is necessary to furnish 100 million gallons per day—the capacity of the old aqueduct.

Can it be that the completed aqueduct is not "turned on" because it would now bring no greater volume of water to the city than the old one?

When the Sodom dam is completed, say in 1893, the storage will be increased, but the city also will have increased to such an extent that the deficiency of storage will then be 16 thousand million gallons. In case the new aqueduct is courageously put into use by the summer of 1893, the total aqueduct capacity will then be 350 million gallons per day, while the volume furnished by the reservoirs will be 135 million gallons.

Will the deficiency be made up in 1897? By this time the demand of the city will have reached 250 million gallons per day, and the storage computed to be necessary is 43 thousand million gallons. Now, the maximum storage capacity of the Croton basin, without the Quaker Bridge dam, is 20 thousand million gallons; and since it is practically out of the question to finish this latter structure before the year cited, there will then be a deficiency of 23 thousand million gallons, and more, too, unless all the smaller reservoirs are completed in the interval, which is so improbable that it is safe to assert that the two aqueducts together will not convey in the dry season of 1897 more than 140 million gallons per day.

Now the question arises, Will the aqueducts even in mid-summer convey a volume approximating to their capacity? According to the meteorological record of

the Croton Aqueduct Department, the maximum volume of water obtainable is 270 million gallons per day (80 million gallons less than the aqueducts can deliver); and since the city will need this volume during or before the year 1899, it is certain that even if the projected dams are then in service, the deficiency of storage would only be made up for a brief season.

To state the whole matter in a different way, we might say that during the next ten summers sixty per cent of the joint capacity of the aqueducts cannot be utilized. What can be the gain in adding to the expenditure in this drainage area, when the greatest possible effort can only remedy the present deficiency ten years in the future, and then only for a short period?

The conclusion is unavoidable that the Croton basin was too limited to warrant the construction of the second aqueduct, and does not warrant the construction of more dams now—hence the scheme's independence of surveys and records of rainfall.

If all future expenditure be devoted to bringing water from an elevated watershed that will afford 500 million gallons daily, the deficiency existing to-day can be made good in five years, the pressure can be restored, and the quality of the supply improved.

SPEED TRIALS OF A BRITISH SQUADRON.

The British Mediterranean squadron recently had a four hours' trial of speed between Cagliari and Port Mahon, the result showing that, in a seaway only fairly heavy, an enemy's mercantile traffickers, if ordinarily fast steamers or even sailers—for a quick-heeled sailing craft with a gale behind her is good for 15 knots—have little to fear from any ship now in the Mediterranean squadron, and any craft purporting to be a warsman not fast enough to distance it nor armored to stand and fight would scarce deserve a better fate than to fall a prey.

The trial was under the British Admiralty orders that squadrons must try the speed of their ships quarterly, the day being set long in advance, so that nothing better than ordinary condition of wind and sea may be expected. The wind was a head one, what there was of it, a "moderate" swell running. Here is the tally of the four hours' run, the measure being in knots: Benbow, 61.5; Scout, 58; Phaeton, 57; Colossus, 56.5; Edinburgh, 51; Temeraire, 50.5; Dreadnaught, 49. From this it will be seen that the best time made was the Benbow's, averaging scarcely 15.4 knots an hour, the others in their order averaging 14.5, 14.2, 14.1, 12.7, 12.6, 12.0.

When the speed of these several ships is compared with what they are credited with upon the measured mile, the disparity is wide—further evidence, surely, that practical tests, under ordinary conditions, are the only ones worth the care and expense of making. If the sea were always smooth, save at odd and widely separated intervals, a run along the measured mile or along the channel of a sheltered river would be a fair test. But the contrary is the case. It's nearly always rough, sometimes heavy seas running with the wind, sometimes running against or athwart it, with a nasty swash resulting, and again swelling as with subterranean convulsion. Hence the measure of a ship's efficiency should be on the broad seas in ordinary weather.

A curious and interesting feature of the recent test was the behavior of the Temeraire, which, notwithstanding her aged boilers and lofty spars, she being ship-rigged, ate into the head wind, fairly up with most of the more modern craft, though they were without top hamper, indeed, beating one of their number, the Dreadnaught, for which so much had been promised.

It is only a natural inquiry how such ships as those composing this squadron could destroy an enemy's commerce that should be carried in steamers like the City of Paris, the new Hamburg-American steamer Columbia, the City of New York, Augusta Victoria, Etruria, Umbria, and many more that could be mentioned? How could they prevent the commerce of their own country from being destroyed by these swift craft, a few light guns being mounted on their main decks?

A New Joint-Making Material.

A permanent and durable joint can, it is said, be made between rough cast iron surfaces by the use of mineral asbestos mixed with sufficient white lead to make a very stiff putty. This will resist any amount of heat, and is unaffected by steam or water. It has been employed for mending or closing cracks in cast iron retorts used in the distillation of oil and gas from cannel coal. The heat being applied to the bottom of the retort, and the temperature of the iron maintained at a bright red heat, after a time the bottom of the retort would give way, the larger portion of the crack being downward toward the fire. The method employed was to prepare the mixture, and place it on the top of a brick, then put the brick on a bar of iron or shovel, and press the cement upward to fill the crack in the iron, holding it for some time until it had penetrated the cavity and somewhat set. Of course, during this operation, the lid was removed from the retort, so that no pressure of gas or oil forced the cement outward until set.

CONSTRUCTION OF NEW RESERVOIRS FOR NEW YORK WATER SUPPLY.

Very few are aware of the magnitude and nature of the work that is being carried on with a view to improving the water supply of New York City. Ever since the late public examination into the aqueduct contracts and into their proper, or rather improper, fulfillment, public interest in this great engineering work appears to have flagged. Even the daily press, which at that time was filled with leaders on what they deemed a public scandal, has lapsed into silence, and little is ever heard of the present condition of this work. It is possible that the very rainy seasons of this and last summer have been the cause of this public indifference to our present inadequate water supply. Whether the problem will be solved by the methods proposed or not, from an engineering point of view the work possesses great interest, and the description on another page shows how far the work has progressed. The work we allude to is the construction of two dams on the Croton River, which serve to furnish two large reserve reservoirs to be called into service in case of the failure of Croton Lake. The map on page 103 shows the geographical situation of these dams. These bodies of water will be known as Sodam dam reservoir and Bog Brook reservoir. Collectively they will have an estimated capacity of 9,000,000,000 gallons, or nearly four and one-half times the capacity of the present Croton reservoir.

As will be seen by examining the map on page 103, the amount of work that has been finished and that is in course of completion is very small in comparison with the vast bodies of water that will eventually be stored for the use of this metropolis. Nothing has yet been done to Quaker Bridge dam, and the opposition that has been offered to its construction has been so great that other points on Croton River have been examined in regard to their availability. Borings have been made at four places between Croton dam and the proposed site of the Quaker Bridge dam, and it is possible that some new and definite plan will be proposed before many months.

In case the borings show that a rock bed can be reached at a less depth, it is probable that such a site would be preferred to the Quaker Bridge, even though it were necessary to construct a dam of greater length; and surveys are now being conducted at several points of the river where the banks are farther removed from one another to decide upon this question. We purpose in an early issue to follow this article on the Sodam dam by an article on the present condition of work at an interesting point of the new aqueduct.

[SPECIAL CORRESPONDENCE OF THE SCIENTIFIC AMERICAN.]

The Paris Exhibition.

THE WOODWORKING MACHINERY.

PARIS, August 1, 1889.

American woodworking machinery is conceded even by its European competitors to be surpassed by none, and there is no doubt that most of the new improvements and applications in this class of machinery not only originate, but have to be developed, in the United States before they are copied on this side. George Richards, of Manchester, has done a good deal toward showing in England the advantages of some American designs, and of course this has been an uphill fight, as pioneer work always is, the Baxter D. Whitney scraping machine being a prominent example. There is no European equivalent of this machine. Mr. Whitney, by the way, brought over, on his recent visit with the American joint engineering societies, two exceedingly interesting pieces of work. One is a sample of wood planing consisting of a piece of stuff about $\frac{3}{4}$ inch planed down to a thickness of about 1-100 inch, with a clean and almost polished surface, and it is conceded on all hands to be a matchless piece of work. The other is a right and left hand screw, upon which I propose to have something to say at a future time. Speaking of samples of woodworking reminds me that in some of the large woodworking machine manufactories in England I have seen samples of woodworking that came from the United States and that were used to show what certain classes of machines could do.

The principal exhibit of woodworking machinery is that of J. A. Fay & Co., of Cincinnati, Ohio, and a very fine exhibit it certainly is for quality as well as quantity, while it is thoroughly representative of advanced American practice.

Beginning with the No. 4½ heavy, four-side, patent moulding machine, we have here a solid, substantial machine, mechanical-looking in every detail, and remarkable for the ease and rapidity with which it can be handled when at work and adjusted for different kinds of work. There are two feed rollers above and one below the platen, the upper one nearest the cutter head being small in diameter, so as to bring it as near as possible to the knives. The lower feed roll, on the other hand, is of very large diameter, and runs in adjustable bearings. The upper feed rolls are carried in swinging yokes, so that, while they always rise parallel with the stuff being worked, yet they can be swung out of the way in an instant to get at the cutters. There

is a wood pressure shoe both back and front of the cutter head.

The two side heads and the under head are carried with their bed, so that when these heads are once adjusted, the bed may be raised or lowered for different thicknesses of stuff without disturbing their adjustment. The two side heads may be adjusted vertically and set to any required angle up to 45° and may be adjusted laterally to suit the width of the stuff or of the work. The lower cutter head has an end adjustment and is carried on the same bed as the side heads, so that when these three heads are adjusted, the bed may be raised or lowered at will without altering their adjustment. The opening in the bed for the lower head has movable plates to adjust the width of aperture to suit the depth of cut or the size of the cutter heads.

The upper cutter is furnished with an outside bearing that is a great improvement for fine work, as it steadies the head and prevents vibration.

We now come to a distinguished feature of the machine, namely, its convenience of handling. The handwheel for raising or lowering the platen, the checking lever for securing it in its adjusted position, the lever for starting and stopping the feed, the wheel for adjusting the height of the side heads, and the bolt for setting them to an angle, the handles for their lateral movement, and the wheel for the end adjustment of the lower head are all on one side of the machine and within easy reach of the operator, as he stands in his natural position at the machine with the work going on before him.

The next machine to claim attention is the No. 5 patent band resawing machine, and this brings to mind the curious fact that, while the French are the inventors of the band saw, it is in the United States that band sawing machines have been brought to the highest state of perfection, indeed the reciprocating frame saws so much found in the Arbey practice and in England cannot compete in the United States with the self-feed resawing machine.

The machine before us is a combination one, inasmuch as that the table carrying the roll feed mechanism may be turned upside down, taking the feed rolls, etc., entirely out of the way and leaving the machine a plain band sawing, but the solidity and usefulness of the machine is in no way sacrificed to obtain this double service. The machine is designed for reducing deals to lumber or resawing boards to thin stuff, as for panels, picture backing, or splitting veneered panels. The saw is but 20 gauge, producing a kerf of less than one-sixteenth inch. Some of the work I saw produced on this machine in the exhibition was less than one-sixteenth thick and as parallel as could be. All four of the feed rollers are driven both sides, being adjustable to or from each other, while one pair of rollers is made yielding, to keep the feed pressure constant, notwithstanding inequalities in the lumber or stuff. The rate of feed is regulated by a friction disk, which can be adjusted without stopping the machine to give any rate of feed from 5 to 40 feet per minute.

Next may be noticed the improved miter and bevel saw table. This class of machine finds increasing favor every year, doing much of the work formerly assigned to the band saw. The fact is that setting a band saw table out of the horizontal for bevel work makes it very troublesome to handle the work, and this machine gets over that difficulty by using a circular saw so mounted beneath a fixed horizontal table that, while it will swing 45° out of the vertical, yet the opening through the table is no wider than it would be if the saw ran in a vertical plane only. The adjustment of the saw either for height or angle can be made while the machine is still or running. Suitable fences and gauges of course accompany the machine. We now come to a self-feed rip saw in which a serrated feed wheel no thicker than the circular saw, and set in line with it, is used. This class of machine finds much favor on account of its simplicity for a self-feeding machine. The table is fixed, the saw raising and lowering through it for adjustment to the work. A simple train of gearing that is covered in drives the feed wheel, and a spring guard covers the saw and holds the end work in place, so that it shall glide smoothly along as it leaves the saw and not catch. A suitable fence having a parallel motion is provided, all the handles for working the machine being conveniently situated within reach of the operator.

The most important machine in the whole of this exhibit is perhaps the patent lightning flooring machine, which possesses some interesting and novel features. To begin with, the machine is exceedingly well proportioned throughout. It looks stiff and substantial without being ponderous, while the workmanship is much better than is usually bestowed upon woodworking machinery (a fact, however, that applies to this whole exhibit.)

The machine beads as well as cutting the sides and edges or matching, and some of its notable features are as follows: In addition to the ordinary feed rolls, there is a feed roll revolving in a horizontal plane, and therefore giving an edge feed to the board while keeping it up to the fence—a valuable feature. Then the

fences for all the beads move simultaneously and equally (a feature of special merit). The side beads either adjust together or independently, as may be required, carrying their gauges with them. All parts of the machine are easily got at for adjustment, etc., and the handles, etc., for operating it are conveniently got at, handiness having been carefully thought out.

There are two tenoning machines in the exhibit (both suitable for heavy work, but one larger than the other), one having a hand feed only, and the other an automatic feed as well. The latter is a gap machine, which increases its capacity and enables it to serve for gaining purposes. The top and bottom head are adjustable either independently or simultaneously on their vertical slides, the top spindle being carried in a gateway or slide that enables it to be adjustable endways. The power feed is operated by cone friction disks, the carriage running on friction rolls.

The lower head is lowered out of the way when gaining is to be done, the gaining heads going on the top arbor, and being capable of expansion to double its normal capacity. Thus a three inch head will make a gain anywhere from 3 to 6 inches wide, and so on for all sizes.

A cabinet maker's double circular sawing machine exhibited has two saws (one a rip and the other a cross cut) on independent spindles, one iron table serving for the two. There is a space between the two saws, however, that can be thrown back to allow free access to the saws. Either saw can be replaced by heads for rabbeting, gaining, dado work, or plowing. The table on the up saw side is fitted with an adjustable fence which can be set to any required angle and is movable in planed ways to or from the saw. On the cross cut side a cutting-off slide is provided with suitable stops for cutting off to length and adjustable to various angles. T slots for miter or cutting-off slides are provided for each saw.

In the Strifflers patent double cut-off sawing machine four saws are provided, two being in a table fixed at one end of the frame and two in a table adjustable along the frame, but which may be instantly locked in its adjusted position. Each table has one arbor which carries a saw on each end and is in a frame which is raised and lowered by a hand wheel in front. Wood packing plates are inserted in the tables around the saws, which can be removed for grooving purposes. The machine will cut off to exact length anything from 6 inches to 6 feet long, the sliding cross cut gauge being provided with stops (for cutting to exact length), and so arranged that one operator can work with the grooving saw and another cut off both ends of the work at once to any length from 22 inches to 5 feet without using any sliding carriages. In a No. 2 patent automatic railway cutting-off saw machine in this exhibit the saw is traversed back and forth by a chain feed put in operation by a foot lever. The guide rails for the traveling carriage are cast solid on the frame to secure rigidity. Adjustable stops regulate the distance the saw travels. The feed motion of this machine is very simple and ingenious, the foot lever that governs it serving to cause the table to traverse in either direction, and when uninfluenced by the operator's foot, throwing the feed out altogether. The cutting-off machine part of the exhibit is completed by a vertical cutting-off and mitering machine, in which the saw carriage is operated on a vertical slide, the feed screw being operated in either direction by three bevel friction wheels at the base of the machine, a single treadle being so constructed that it will throw the clutch to the right or left, according as the saw is required to travel up or down. A stop motion for the limit of descent is provided by a rod from the carriage to the treadle rod, which throws the clutch out of gear when the saw has descended or ascended to the required distance. The notice of this exhibit may be concluded for the present with the planer knife grinding machine, in which the end face of a hollow cylindrical emery wheel is used for the grinding. The table traverses automatically to a determinate point, and continuously without attendance after the machine has once been adjusted, a stop motion causing the grinding operation to cease when sufficient has been ground off to resharpen the knife. If it be desired to grind the knife concave, the head carrying the knife swivels, by which means the amount of concavity may be varied at will within certain limits. It may be noted that concave grinding is less in vogue than formerly, as, being very thin or not well backed up by metal behind it, it is tremulous and does not produce smooth work.

JOSHUA ROSE.

Utilization of Running Streams.

The utilization of running streams is the object of many recent devices, among which may be mentioned that of M. Tain, a Russian engineer. His apparatus consists of an endless cable, carrying a series of canvas cones, which open and shut like an umbrella. The cable passes over a double drum on board a pontoon, and at the other end over a pulley suspended from a buoy. On the lower part of the rope the cones are opened and forced forward by the current of water, thus setting in motion a shaft or drum.

AN IMPROVED UMBRELLA STAND.

A device whereby a number of umbrellas may be rigidly held in such position as to present an attractive appearance is shown herewith, and has been patented by Mr. Jonathan Haight, of Pittsfield, Mass. The body of the stand has shoulders one above the other, the lowest shoulder being the largest, there being on the inner side of each of these shoulders, next the body of the stand, a V-shaped groove, in the bottom of which is a series of cavities, each adapted to receive the ferrule of an umbrella. To each of the shoulders is attached a disk having a series of essentially oval shaped openings to receive each an umbrella, and give it an inclination upward and



HAIGHT'S UMBRELLA STAND.


outward. In the top of the base of the stand vertical rollers are arranged upon a concentric line, the rollers being countersunk in the base in such manner that they will project but slightly above it, whereby the stand may be revolved and the umbrellas made to face in any given direction.

AN IMPROVED LOCKING BUCKLE.

A buckle in which the tongue is positively locked against the buckle frame is shown in the accompanying illustration, and has been patented by Mr. William Blum, of Newark, New Jersey. Figure 3 is a plan view of the buckle and its key, partly in section, Figure 2 being a side view of the locking bar detached, and Figure 1 a perspective. The front bar of the buckle frame is hollow and centrally notched for the entrance of the point of the tongue. Within the front bar is fitted a spring-actuated locking bar, angular at its inner end to prevent its turning, and threaded on its other rounded end to receive an internally threaded key, for partly withdrawing the locking bar against the tension of a spring coiled around it. Just beyond its center the locking bar is notched, and a longitudinal slot extends toward the center from the bottom of this notch for locking the tongue. The key is used to move the locking bar outward until its notch registers with the notch in the front bar of the buckle frame, and, when the key is removed, the spring pushes the locking bar inward, so that the notches are out of register, preventing the withdrawal of the tongue except by the use of the key.

AN IMPROVED CAR COUPLING.

An automatic car coupling in which a pivoted pin or dog is employed to engage the coupling link and hold it in position in the drawhead, and in which the parts will always be in a position for automatic coupling after the cars have been uncoupled, is illustrated herewith, and has been patented by Mr. Charles W. Chisholm,



CHISHOLM'S CAR COUPLING.

of No. 11 Patrick Street, Winnipeg, Manitoba, Canada. Fig. 1 shows a central longitudinal sectional view of the device as applied, Fig. 3 being a perspective, and Fig. 2 an end view of the drawhead. Within a vertical slot in the top of the drawhead a coupling dog is mounted, supported by a pivot passing through an aperture of larger diameter than itself in the dog. When in the coupling position, the lower portion of the dog rests within a recess in the bottom of the drawhead, the rear portion of the lower projection of the dog constituting the bearing face. As the link enters the drawhead, and strikes against the forward inclined face of the dog, the latter is forced to the position shown at the right in Fig. 1, the dog dropping back, when the link has passed in, to the position shown at the left in the same figure. The dog extends somewhat above the top of the drawhead, where it has a handle or lug, connected with a lever extending to each side of the car, by which the dog is manipulated. The dog may be locked in such position that the link may be withdrawn by lifting the dog until a shoulder thereon is brought into engagement with a notch in the top of the drawhead, but as the link is drawn out of the link recess it strikes against a projection of the dog, whereby the latter is returned to the position shown at the left in Fig. 1. A metallic cover is provided to prevent the entrance of gravel, snow, etc., when the parts are in coupling position.

Medicinal Properties of Vegetables.

The following information may be useful to some at this season of the year, if not new to many:

Spinach has a direct effect upon the kidneys.

The common dandelion, used as greens, is excellent for the same trouble.

Asparagus purges the blood. Celery acts admirably upon the nervous system, and is a cure for rheumatism and neuralgia.

Tomatoes act upon the liver.

Beets and turnips are excellent appetizers.

Lettuce and cucumbers are cooling in their effects upon the system.

Onions, garlic, leeks, olives, and shalots, all of which are similar, possess medicinal virtues of a marked character, stimulating the circulatory system and the consequent increase of the saliva and the gastric juice promoting digestion.

Red onions are an excellent diuretic, and the white ones are recommended to be eaten raw as a remedy for insomnia. They are a tonic and nutritious.

A soup made from onions is regarded by the French as an excellent restorative in debility of the digestive organs.

OPERATIVE DENTISTRY—FILLING TEETH.

Dr. Charles H. Land, of No. 264 Woodward Avenue, Detroit, Michigan, has invented and covered by several patents a means of restoring decayed or imperfect teeth to their original shape, size, and color. The invention provides a method of moulding vitreous or other substance into sections corresponding to the form of the lost portions of decayed teeth, by swaging or burnishing a thin metallic matrix of suitable metal into the cavity of the tooth, and producing with such matrix a solid section or plug of any desired material corresponding to the shape of the cavity in the natural tooth, this plug being fixed in position by suitable cements, either with or without the matrix. The invention also covers the preparation of veneers of all forms and tints, to be kept in stock by dentists, a metallic cover being shaped to the outlines of the tooth to be crowned, the previously prepared porcelain veneer to be fitted to the cover, and fused thereto by an intermediate stratum of porcelain paste.

In Fig. 1 of the illustrations, 1 represents a tooth having a cavity needing filling; 2 and 3 show a matrix fitted to the cavity; 4 shows a filling fitted to the matrix; 5, a complete filling applied in the cavity; 8, another form of cavity in a tooth, and 11, a filling applied thereto; 9, a modification of the metallic mould plate, and 10, a filling fitted thereto; 6, a sectional view, showing the cavity partially filled with a soft filling; and 7, a modification of the matrix and plug for use therewith.

In Fig. 2 1 represents a typical view of decayed front teeth, and 11 shows them restored; 5 is a single tooth prepared for the fitting of the metallic cover; 6 is a modification, with the tooth built up with amalgam or other suitable substance; 7 shows the metallic cover prepared to fit the tooth, and 9 and 10 are side and perspective views of the porcelain veneer to fit the metallic cover, while 8 shows the metallic cover with the porcelain veneer fused upon it. A tooth prepared for a partial enameled cover is shown in 2, and 3 is a sectional view of a partial enameled cover applied to the tooth, 4 showing the cover separately.

In forming the matrix, platinum is preferably employed, although gold and silver or other material may be thus used, and in some cases pins are engaged with the matrix, porcelain, rubber, or glass, and in some instances metal, such as gold or silver, being used to fill it, although porcelain is preferred. The latter, with certain forms of rubber, may be modified in color to

approach the shade of the natural tooth, and will also take a durable polish. The thin piece of platinum plate may be readily swaged into the cavity of a tooth to make a perfect impression, while the porcelain paste built into the matrix may be readily carved or modified to imitate the original contour of the lost portion of the tooth, being then fused in the ordinary manner.

In the use of the previously prepared porcelain veneers, which are made as separate articles of manufacture, expressly for this class of work, a suitable veneer is selected and ground and fitted to its place, when it is engaged upon the metallic cover by using a porcelain body or paste, the cover, veneer, and porcelain body being fused together, the cover with its combined veneer being then cemented upon the tooth.

Dr. Land has also invented what he styles the "Midget" gas blast furnace and blowpipe combined,




Fig. 1.—RESTORING DECAYED OR IMPERFECT TEETH

as an ideal furnace for the operative dentist, and for especial convenience in the fusing operations required with his porcelain fillings. The furnace complete, with blowpipe, stand, and bellows, does not occupy more than ten inches of space, and by its use the dentist can readily fuse high grade porcelain in from six to fifteen minutes. The Hydrocarbon Furnace Co., of Toronto, Canada, has been organized to introduce this furnace and Dr. Land's other dental inventions in Canada.

Dr. J. A. Robinson, of Jackson, Mich., president of the Michigan Dental Association, writes that "the new method invented by Dr. Land is a step forward in the dental art. It is a new method of the old plan of continuous gum work applied to teeth. We have removed large gold fillings in the front teeth and replaced them with porcelain caps, but the process was long and wearisome to the operator and patient. With Dr. Land's method most of the work is done in the laboratory, when the patient is dismissed until the cap is enameled,




Fig. 2.—RESTORING DECAYED OR IMPERFECT TEETH.

and then it is inserted in a very short time. The great advantage of the new system is the most perfect adaptation and the means brought about to accomplish the result by his new furnace and a series of different colored bodies, matrices, etc., to obtain the exact shape and shade of the natural teeth. These fillings are to take the place of all other fillings, from the smallest filling to the entire crown of the tooth."

If not already a subscriber, send 25 cents and have a copy of the Architects and Builders Edition of the "Scientific American" mailed to you. After seeing a copy you will want all the back numbers.

MANUFACTURE OF ROLLED BARS OR RAILS DIRECT FROM THE MOLTEN METAL.

By the method or process heretofore generally in use for manufacturing railroad rails and other metal bars the molten metal is first cast into an ingot, which is then reheated and rolled and rerolled until reduced to the required size and shape. By this method the molten metal is not subjected to compression in the mould while it is in the act of setting, though it is well known to those skilled in the art that the compressing of the molten or setting metal while it is yet in the fluid or setting state tends to greatly improve the character and quality of the steel produced and to give the castings or ingots a very dense, solid, and homogeneous structure; and where, as heretofore, the metal is cast in a closed mould confined on all sides, excepting at the top or runner, air or gases confined in the molten metal have little opportunity to escape, so that it is difficult in this way to produce an ingot entirely free from air holes and imperfections. The rolling and rerolling to shape of the finished bar or rail tends to densify the metal to a greater or less extent; but this rolling operation does not entirely remove the flaws or imperfections produced in the ingot at the time it is cast. The manufacture of metal bars or rails by this old process also involves considerable time, labor, and expense in the several steps of the process, and requires an extensive and costly plant of machinery.

The invention of Edwin Norton and John G. Hodgson, of Maywood, Illinois, consists in pouring a continuous stream of molten metal from a suitable vessel and simultaneously compressing, setting, and shaping the metal by its contact with chilling and compressing surfaces or rolls, which confine or surround the stream on all sides as it passes such continuously-moving chilling surfaces or rolls. The chilling surfaces or rolls which shape, compress, and set the metal, and thus convert the molten stream of metal into a metal bar or rail, travel or move at the same surface speed as the velocity of the flowing stream of molten metal, so that the molten metal will not dam up or collect between the rolls, and so that the molten metal or bar produced will come in contact with the rolls or chilling surfaces only at a single point, so to speak, at a time.

The metal bars or rails, it will be thus seen, are produced directly from the molten metal, and without first casting the metal into an ingot and heating and rolling and rerolling it; and as the molten metal is poured in a continuous, solid stream into what may be termed a continuously revolving or traveling metal chilling and compressing mould, which comes in contact with only one point, or a very limited length of the metal stream or bar at a time, and is continuously traveling in the same direction with the stream or bar, point after point in the whole length of the metal stream or bar coming successively in contact with this traveling or revolving compressing and chilling mould, the metal bars or rails are of course produced in continuous lengths, and the process or operation is continuous so long as the stream of metal flows.

In practice the molten metal is poured in a continuous solid stream, from a suitable bowl or pouring vessel, between a series of rolls, preferably four in number, having their axes arranged in the same horizontal plane and having a pocket or space between their peripheries at their common meeting point for the reception of the stream of molten metal, so that the stream of molten metal, as it passes between the rolls, will be compressed by the wedging action of the rolls and the molten metal at the same time chilled or set by contact with the rolls. The rolls are made hollow and filled with water, which is made to constantly flow through them, so as to keep them cool or at the proper temperature for chilling or setting the stream of molten

metal as it flows between the rolls. The pouring bowl or nozzle is arranged directly over the common meeting point of the series of rolls, so that the stream of molten metal will flow in a direction tangential to all the rolls. Each roll thus comes in contact with the stream of molten metal, or with the metal bar produced, only at a single point, so to speak, of its periphery at a time, thus making it practicable to easily keep the rolls cool, or at a proper temperature for chilling or setting the



STATUE OF LEVEURIER BY M. CHAPU.
[FOR DESCRIPTION SEE NEXT PAGE.]

stream of molten metal as it passes between the rolls. The rolls are revolved at a sufficiently great surface speed, in respect to the velocity of the stream of molten metal and in respect to the space between the rolls or the size of the bar being produced, as to prevent the molten metal collecting or damming up in the space between the rolls. Large surface contact between the molten metal and the chilling rolls is thus prevented, which would tend to heat the rolls rapidly and render it difficult to keep them cool or at the proper temperature, on the one hand, and which, on the other hand, would tend to chill or set the molten metal before it reaches the meeting line or plane joining the axes of the rolls, and where the passage between them is most contracted, thus subjecting the apparatus to greater strain and requiring greater force to revolve the rolls, and interfering, to a greater or less extent, with the proper compression of the metal while yet in a molten or setting state.

By employing a series of rolls, the fluid or setting stream of metal passing between the rolls is compressed on all sides, thus densifying or compressing the metal by the wedging action of the rolls, and this densifying or compressing action of the rolls upon the metal aids in solidifying or setting the molten metal, as well as to greatly improve the quality of the steel or metal bar produced. The compressing and rolling action of the rolls upon the fluid or setting stream of metal passing between the rolls also tends to give the metal bar a superior texture, grain, or fiber, and thereby to increase the strength of the bar produced.

The process in its most improved or perfected form also consists in pouring a stream of molten metal and simultaneously compressing, setting, and shaping it into a bar, and then further rolling and finishing the bar as it is produced and while still at a high heat. In practicing this latter feature of the invention we preferably arrange directly between the first series of rolling, chilling, and compressing rolls or moulds a second series of revolving rolls, which serve to further chill, compress, shape, and roll the rail or bar as it issues. The con-

tinuous rail or bar produced is delivered from this second series of rolls by an intermediate curved passage or conveyer, consisting, preferably, of a series of rolls arranged in a curve. As the rail or bar is conveyed out horizontally, it may, while still hot, be passed through finishing and straightening rolls and further rolled to a greater or less extent, as may be desired.

A represents the frame of the machine, on which is journaled a series of rolls, B, preferably four in number, revolving together and having their peripheries shaped or grooved to form a passage or way between them to receive the stream of molten metal as it flows down from the pouring bowl or nozzle, C.


The working or meeting faces or peripheries of the rolls, B, are given a shape or configuration to form an ordinary railroad rail. They may, however, be shaped to give the space or passage any desired cross section, and thus produce a bar of any form required. The rolls, B, have beveled faces, which meet or roll against each other and serve as stops for the several rolls against each other, so that the space or passage for the metal will always be maintained of a uniform size, and thus produce the rail or bar of a uniform cross section throughout. The rolls, B, are each made hollow, and preferably with a central web, and the shafts are also made hollow, so that the water or other cooling fluid or liquid may be made to circulate through each of the rolls for the purpose of keeping them cool or of the desired temperature. The hollow shafts are each furnished with a packing or stuffing box at each end, by which they are connected with the inlet and outlet water pipes, D D'. The pouring bowl or vessel, C, is supported by any suitable means above the rolls, B, during the pouring operation, preferably by standards C', furnished with adjusting screws, C². The pouring nozzle, C, is preferably furnished with a valve or device for opening and closing the discharge passage. The hollow shafts of the rolls are all geared together, so that they revolve or roll together at the same surface speed. The gearing employed may preferably be bevel gears, such as indicated at B³. Two of the shafts, B², are also geared together by spur gears, B⁴. E is the driving shaft, having a gear, E', which meshes with a gear, E², on one of the shafts, B². The pouring bowl or nozzle, C, is furnished with a guide or shield, extending down to near the meeting point of the rolls. This is designed to prevent the metal from splattering at the beginning of the pouring operation. A greater or less number of rolls than four may be employed.

F represents a second series of rolls arranged, preferably, directly below the chilling rolls, B, and between which the bar, x, passes as it issues from the chilling rolls, B. Rolls, F, are preferably of the same form and construction as the rolls, B, being hollow and having the same connections for passing water through them, so that they may operate as chilling rolls as well as to further roll, compress, and finish the rail or bar produced.


G is a curved guide or conveyer consisting, preferably, of a series of rolls or idle pulley wheels, arranged in a curved path to curve and guide the bar as it issues from the rolls, F, to the horizontal conveyer or series of rolls, H. Some of the rolls, H, are preferably driven and operate to further roll and straighten the rail or bar, as well as to convey it along or away. The curved guide, G, also affords some slack in the rail or bar between the chilling rolls and rolls, H H, to compensate for difference in speed or slipping.

ROBERT'S NEW PROCESS OF CONVERTING CRUDE IRON INTO MALLEABLE IRON OR STEEL.

The converter, after being charged, is tilted, as shown in Fig. 1, and the blast is applied upon or so near to



MANUFACTURE OF BARS AND RAILS DIRECT FROM THE MOLTEN METAL.



THE ROBERT PROCESS.

the normal surface of the metal in the bath and is so directed thereto that it will not enter or penetrate the body of the metal as in former processes, and so that practically no portion of the metal will be above the blast, and in such manner that only a small portion of the metal will be subjected to the action of the blast at any one time. Thus, as the blast passes inward through the tuyere at a point adjacent to the surface of the metal, its rapid forward motion, combined with the tendency to escape upward in the direction of least resistance, gives to the blast and to the portion of metal carried therewith a resultant diagonally upward direction away from the main body of metal, so that small portions only of the metal are thus acted upon and stripped off at one time; but as such small portions are subjected to the impact of the entire blast, a much more violent agitation is imparted thereto by a comparatively light blast than it would be possible to impart to the entire body by a blast of the most powerful character, and as a result of this agitation not only are the particles of impurities separated from the metal, but the latter is so atomized that it is spread or divided into small particles as to present the desired extended surfaces required to effect the speedy and thorough oxidation of all particles. The action of the blast in carrying a portion of the metal to the opposite side of the converter is to pile up the metal at that side, which, together with the impact of the blast on the exterior portion of the body of metal, results in the production of a circulatory or gyratory current in the direction of the arrows, which causes a flow of the metal downward and upward toward the area of violent action, while the metal is prevented from rising above the line of the blast by the impact of the latter, which strips or beats off the particles presented in its path, so that an inclined surface is imparted to the bath at one edge lower and at the other higher than the mouths of the tuyeres. As a result of the more perfect and rapid oxidation from the more thorough admixture of the atoms of air and metal, there is a higher temperature, inasmuch as there is a more complete and uniform conversion, and because, owing to the limited portion of metal acted upon at one time, every portion may be thoroughly oxidized. The temperature of the bath is therefore not only maintained as the result of the action of the blast, but is increased, so that the metal is rendered extremely fluid, thereby facilitating its movements under the action of the blast and preventing its rapid cooling when removed from the converter.

The blast must not be too deep or it will enter into the body of the metal, while on the other hand it must be deep enough to come into sufficiently extensive and intimate contact with the metal to produce the necessary reactions and conversion, or it will escape without producing the desired results; but it must be remembered that the bulk of the metal diminishes during the conversion by reason of the elimination of the impurities. Consequently the level of the surface of the metal falls during the process, and therefore the blast must be varied to maintain its position relatively to the metal. This may be done in various ways, two of which naturally present themselves—first, by bringing the blast down to the metal, and, second, by bringing the metal up to the blast. The former proceeding may be most conveniently accomplished by using a tilting converter and turning it upon its trunnions during the progress of conversion to different positions, as indicated in Figs. 1, 2, and 3, to vary the ferrostic pressure against the blast as the process continues, or in a fixed converter, by having the tuyeres movable and dropping them as required. By thus adjusting the relative positions of the blast and metal a continuous supply of new or fresh metal can be brought into the area or zone of conversion in such exactly regulated quantities as will maintain the proportion of the metal acted on relative to the volume of air as is necessary to the production of the best results. The raising of the level of the metal could be effected by adding more metal or by means of a false bottom, which would raise the whole of the metal, or otherwise, so as by occupying part of the space previously occupied by the metal to restore the surface level.

By tilting the converter or otherwise varying the amount of metal presented to the action of the blast, the extent to which the metal is divided or atomized may be regulated at the will of the operator, and by thus throwing the iron by a regulated action into a sort of spray, or minutely subdividing or atomizing it, the largest possible surface is presented to the atmosphere, and the particles of carbon, silicon, and phosphorus, or other combustible matter, are exposed and commingled with the oxidizing agent, and there is a rapid and intense combustion of said combustible elements and such a high temperature is imparted to the metal as renders it extremely fluid and mobile. The extent of the spraying action will depend on the extent to which the metal is presented to the spraying means. As this is regulated at the will of the operator by the means described, the feeding of the metal, the rapidity of the conversion and degree of heat, and the degree of the fluidity of the metal may all be controlled.

INAUGURATION OF THE STATUE OF LEVERRIER.

The statue raised to the memory of the eminent astronomer Leverrier was inaugurated on the 27th of June, in the court of honor of the observatory.

The Minister of Public Instruction and of the Fine Arts, after being received by Admiral Mouchez, director of the observatory, took his place under the tent raised opposite the monument. Among the distinguished spectators grouped around him were remarked all the notabilities of science. Several addresses were made: first, one by Mr. Fizeau, of the Academy of Sciences, who, addressing himself to the minister, offered through him to the state the monument raised by a national subscription begun by a number of scientists and friends of Leverrier.

Admiral Mouchez afterward thanked the committee, and especially Mr. Fizeau, the active president of it, for the monument.

Mr. Tisserand afterward spoke in the name of the Bureau of Longitudes, and finally Mr. Bertrand, perpetual secretary of the Academy, made the apology of Leverrier.

Mr. Fallieres, in a few words, responded to the eloquent and precise discourse of Mr. Bertrand, and, after this, delegations from all the academies and all of Paris' scientists came to salute the minister and the director of the observatory.

The beautiful statue, which stands on the avenue that leads to the central pavilion, is the work of Mr. Chapu. Leverrier is represented standing, with a celestial sphere in front of him. Upon the pedestal, which is of some little height, is engraved the following inscription:

U. J. J. LEVERRIER.
1811-1877.

The bass-reliefs sculptured on the stone represent, the one at the left, Astronomy tracing the orbit of the planets; and showing the planet discovered by Leverrier the one at the right, Meteorology, designating, with the hand, the observatory, whence proceed all discoveries.

This beautiful work has already been much remarked at the Salon, where it figured in 1883.—*Le Monde Illustré*.

LEVERRIER.

Urbain Jean Joseph Leverrier was born in St. Lo, March 11, 1811, and died in 1877. After a course of study at the colleges of St. Lo and Louis le Grand, he graduated at the Polytechnic School. Obtaining a place in the tobacco bureau, and finding that that occupation required some knowledge of chemistry, he pursued the latter science at leisure, and, in 1837, published two memoirs on the combination of phosphorus with oxygen and hydrogen. Mathematics, however, became the principal object of his study, and from his proficiency therein he soon obtained a minor appointment in the Polytechnic School. From this time on he directed his studies toward the elucidation of the highest problems in speculative astronomy, investigating, especially, the irregularities manifested in the course of the heavenly bodies.

Two memoirs on this subject, presented to the Academy of Sciences in 1839, attracted the attention of Arago, who, becoming his friend, induced him to study closely the orbit of Mercury and its perturbations. In 1844, he presented two important papers on comets to the Academy, and the importance of these contributions to science caused him to be elected to the astronomical section of that body. The success that had attended his calculations of the course of Mercury induced him to revise the still more imperfect tables of Uranus. After a thorough study of the subject, he became convinced that the movements of the latter planet could not be explained by the attraction of any known bodies, and he therefore sought further for the cause of its perturbations. At length, on June 1, 1846, he indicated to the Academy, within ten degrees, the place where a new planet might be seen January 1, 1847. This was, in fact, seen by the German astronomer Galle four months before the time indicated, viz., on September 23, 1846. Leverrier had erred, but by a difference of only two degrees.

This discovery caused an immense sensation, and Leverrier received abundant honor. Most of the learned societies of Europe inscribed his name on their lists; the King of Denmark sent him the Order of Dannebrog; Salaudy, the Minister of Public Instruction in France, had his bust erected in public with great ceremony; Arago declared that the new planet should be called Leverrier; a chair of mathematical astronomy was created for him in the Faculty of Sciences; the Royal Society of England sent him the Copley gold medal; and the Grand Duke of Tuscany sent him a splendid bound copy of the works of Galileo. The planet bore the name of Leverrier for but a short time, that of Neptune being subsequently bestowed on it.

In 1848, Leverrier made some ineffectual efforts to become distinguished as a democratic leader, but it was not till 1849 that he was elected to the legislative assembly from La Manche. Modifying his liberal views, he devoted himself to questions of public instruction

and laws relative to scientific discovery. Upon a division of the parties in the Assembly, he joined the Imperialists. After the *coup d'état*, in 1857, he became senator, and subsequently inspector-general of public instruction. In 1849-50 he read to the Academy the result of his new investigations into the movements of the planets, and in 1853 he presented to the same body tables of the sun's rotation, with the complete system of the small planets situated between Mars and Mercury.

On the death of Arago, in 1853, Leverrier succeeded to the title and authority of director of the observatory. In 1859 he communicated to the Academy a movement of the perihelion of Mercury, which could only be accounted for by supposing another planet, or a series of small bodies, moving between it and the sun. This brought out Dr. Lescaubault's assertion of his discovery of a planet in 1859, and which he named Vulcan. Subsequent researches, however, have failed to establish the existence of such a planet. In 1870 Leverrier withdrew from the office of director of the observatory, and was succeeded by Delaunay; but the latter having lost his life by drowning, Leverrier was reappointed in 1872.

During the Franco-German war Leverrier offered his services to the Government of National Defense, which employed him in perfecting a system of optical telegraphy which he had invented, and which was intended to render communication possible with Rouen or Orleans by using the light of the sun reflected from a mirror, and astronomical telescopes sweeping the horizon in a given direction. The illustrious astronomer succeeded, after a few months, in devising a complete system, but the Prussian invasion had driven the French forces to such a distance that the curve of the earth opposed an insurmountable barrier to the working of the signals. This system was afterward presented to the Academy, and has since been used with great success by the British army in Afghanistan and Central Africa.

One of the creations of the latter days of the great French astronomer was the system of transmitting the hour by electricity, so as to obtain a uniformity of time in public clocks.

A Warning for the Bathing Season.

A writer in one of our contemporaries, in summing up the causes for so many bathing accidents, concludes that most of them are mainly or entirely personal, and so far preventable. Chief among these, we need hardly say, is cramp. To a large extent this is practically identical with fatigue, for it is not the fresh and vigorous muscle which most readily passes into spasm. It is that which is wearied with over-action, in which effete products are in excess, nutrition consequently impaired, all molecular changes languid; where, finally, the movement of contraction, once initiated, gives way but slowly, and tends to linger and become tetanic. The numbing influence of cold is another well known obstacle to muscular activity, and for this reason it is not as a rule advisable to remain more than a few minutes in the water. Malnutrition of muscles is a factor which ought not to be forgotten. It supplies a reason why bathing very soon after a meal is not advisable, much of the blood required for muscular exertion being then diverted to the digestive organs. So likewise must it impose a check upon the rashness of those, adult and youth alike, who after a period of town life, with little physical exercise, find themselves at the coast, and insist on trying whether with jaded energies they cannot safely accomplish feats of swimming. Yet one more caution. This is that every bather should know the state of tide, the currents, and the ground. Unless he is thus careful, he may find himself at any time confronted by unexpected dangers, the end of which it is impossible to foresee. It may seem ridiculous to urge that only those who really can swim should bathe in deep water, yet neglect of even this precaution is by no means uncommon.

A Water Spray Electrical Influence Machine.

At a recent meeting of the Physical Society, London, the above instrument was described by Mr. George Fuller. The apparatus is made up of four similar sections, each consisting of a nozzle, a metal ring, and a metal dish or receiver, arranged about a vertical axis. Pressure water issues from perforations 1-100 in. in diameter in the nozzles, and passes through the rings into the insulated receiver below. The rings are placed at such a distance below the nozzles as to be about the point where the streams break into spray, and the receivers empty themselves automatically. Calling the consecutive sections 1, 2, 3, 4, respectively, the rings of 1 and 3 are connected to the receiver of 4, and those of 2 and 4 to the receiver of 1. The discharge points are connected with the receiver 2 and 3, and a rapid succession of sparks passes when the water is turned on. Professor S. P. Thompson inquired whether the length of the spark was limited by leakage along the glass rods or by the spray passing between the receivers, and in reply Mr. Fuller said he thought the former leakage the most important.

Correspondence.

Hotter in Utah than in Siberia.

To the Editor of the Scientific American:

In your issue of July 20 there appeared an article headed, "The Great Heat of Siberia," wherein you state that, according to the report of Mr. Geo. Kennan, it is, in summer time, "about as hot a country as there is on the face of the globe." And in his report Mr. K. states the temperature to have varied "day after day from 90° to 108° in the shade."

I thought I would take this opportunity to inform you, and through you the public, that Americans need not go to either Africa or Siberia in order to see the thermometer climb up to 108° in the shade. For if this is the maximum temperature of those countries, they cannot begin "to hold a candle" to either Southern Utah or Arizona. It was only yesterday when in this "Dixie" land of ours (as a portion of Southern Utah is called) we enjoyed the comfortable or uncomfortable temperature of 113° in the shade of a great tree and in a free draught (according to Signal Service instructions and according to a Signal Service thermometer). During the month of June this same thermometer registered a temperature varying from 83° to 107° and an average of 101½°.

During the present month, as far as it has gone, it registered from 91° to 113°.

During the last ten days it stood as follows:

July 18.....	100½°	July 23.....	108°
" 19.....	108°	" 24.....	104°
" 20.....	107°	" 25.....	107°
" 21.....	105°	" 26.....	112°
" 22.....	106°	" 27.....	113°

Maximum temperature by Signal Service thermometer.

Last evening, at 6 o'clock, I laid my own thermometer out in the sunlight for experiment, and it went up to 130°, while it indicated 102° during the whole afternoon in my rooms.

To-day I again laid it out in the sunshine at 2 o'clock in the afternoon, when it went up to 162°. The metal portion of the thermometer, which is designed to protect the bulb, but does not touch it, was hot enough to burn one's fingers, and so is every piece of metal which is left out in the sunshine any length of time. This latter instrument is a confectioner's thermometer, and will register 400°, and is laid in wood.

It is true that the present season has been the hottest by three degrees for several years, and by at least one degree for many years past; but when this place was first settled 119° to 120° was the usual midsummer heat, so I am told. This latter temperature may be found to-day in Fort Yuma, Arizona, and on some of the deserts between there and here the temperature generally runs up to 124° in the shade and higher, so I am informed. But in spite of all this heat a case of sunstroke was never heard of in this region of the country. Several people have perished on the above mentioned deserts for want of water, but in the settlements nobody is ever very seriously inconvenienced, although a good many *think* they are suffering terribly from the heat. This uncomfortable feeling is, however, mostly due to fat pork, grease, butter, and similar blood-heating articles of food. This place (St. George) is situated in a valley about one thousand meters above the level of the sea. All fruits and vegetables in A 1 condition, and grapes are two weeks ahead of other years.

HERMANN FASCHER.

St. George, Utah, July 28, 1889.

P. S.—Thermometer at Signal Service station to-day went up to 115¼°. H. F.

A Simple Relief for Lung Troubles.

It has long been known that pine needle pillows would alleviate persons afflicted with lung troubles, and a Florida editor relates an incident in support of the fact as follows: During a visit to the home of a most estimable lady living on Indian River, this editor was told of a discovery that had been made which may prove a boon to sufferers from lung or bronchial troubles. This lady having heard that there was peculiar virtue in a pillow made from pine straw, and having none of that material at hand, made one from fine, soft, pine shavings, and had the pleasure of noting immediate benefit. Soon all the members of the household had pine shavings pillows, and it was noticed that all coughs, asthmatic or bronchial troubles abated at once after sleeping a few nights on these pillows. An invalid suffering with lung trouble derived much benefit from sleeping upon a mattress made from pine shavings. The material is cheap and makes a very pleasant and comfortable mattress, the odor of the pine permeating the entire room and absorbing or dispelling all unpleasant odors.

The best builders keep on file the Architects and Builders Edition of the "Scientific American." It enables a person about to build to select from the engravings the style of house suiting his fancy and purse.

Artificial Silk.

Science and industry are ever combining to copy nature, and even dare to attempt improvements on her processes. The Champ de Mars contains many illustrations of this; but perhaps the boldest and most curious attempt of this kind is to be seen in the manufacture of artificial silk. Near the end of the Machinery Hall, that end by the Avenue du Suffren, and quite close to the elevator which raises passengers to the traveling bridges, there is an exhibit showing the manufacture of silk without any aid from silkworms, and on a system which appears to be entirely novel and is certainly of wonderful simplicity. The silk industry has seen great vicissitudes and has had to suffer many cruel troubles from disease, both of the worms and of the trees they feed upon, but up to the present we believe that it has been spared the struggles of competition. If this new process should prove to be what it promises, a new and dangerous rival to the silk trade will have to be reckoned with.

The composition of silk may be briefly described as follows: It is a relatively strong, brilliant material, the produce of the digestive juices of the worm acting on the leaves of the mulberry that constitute its food. The cellulose of the leaf is triturated by the worm and transformed by its special organism into a peculiar substance, transparent, and somewhat resembling horn. This is called kerotene, and it fills two glands, from which it exudes in the form of two threads, which unite as soon as they leave the body of the worm; but this material no longer possesses the chemical composition of cellulose. It is largely combined with a new element characteristic of animal tissues—nitrogen. The silk fiber thus discharged forms a continuous thread, which often reaches the great length of 350 meters, the diameter of the fiber being only eighteen thousandths of a millimeter.

It was reserved for the present generation of inventors to devise a means of imitating by science the mechanical and chemical functions of the silkworm.

An old student of the Ecole Polytechnique, M. Le Comte de Chardonnet, set himself some time ago to try and solve the problem. He took as his material pure cellulose, a material, as we have seen, entirely different to that of which natural silk is composed. Cellulose is, as is well known, the basis of vegetable tissues, and particularly of wood; thus all soft woods appeared to be well adapted for the purpose, in fact, any material suitable for the production of a good quality of paper, white wood, cotton waste, etc., appeared fitted for the production of artificial silk; paper pulp is, in fact, the starting point of the industry. This first operation to which the pulp is subjected is that of nitration, which transforms it into pyroxile; this is done by steeping the pulp in a perfectly defined mixture of sulphuric acid and nitric acid. After thorough washing and drying, the nitrated cellulose is formed into collodion by dissolving it in a mixture of 38 parts of ether and 42 parts of alcohol. The collodion thus made is drawn into fiber by the mechanical means which we shall describe presently; but the thread requires further and very important preparation. The fiber, as it issues from the apparatus that imitates the glands of the silkworm, is one of the most inflammable of substances, and in that state would be absolutely useless. An absolute process of denitration is therefore a necessity. Of this operation we can say nothing, because it is kept a secret by the inventor. Its object is, of course, to extract from the filament the greater part of the nitric acid that it contains, and it would be curious to know if the nitrogen that does remain after the process is in the same proportion as that contained in natural silk.

However this may be, the thread after treatment ceases to be inflammable to any marked extent, but it may, if desired, be rendered still less liable to burn. After the denitration process the filament becomes gelatinous, and other substances can be incorporated with it. Thus, when in this state, it can be impregnated with incombustible material, such as ammonia phosphate, and it is at this stage that the filament can be dyed to any desired color. This latter operation cannot precede the denitration process, as all the color would be taken out during that operation.

The mode of manufacture is very simple, and in the exhibition three apparatus are shown in operation to the public. The first of these is only a model to illustrate the principle. The chief feature consists of a glass tube reduced at the upper end to a capillary passage. It is through this passage that the filament of collodion is forced out under pressure. As it issues the fiber is in a pasty state, and would have no consistency if it did not consolidate immediately. This solidification is secured by means of a second glass tube, which surrounds the first one and extends beyond it. Connected to it is a small pipe which supplies a current of water that bathes the collodion filament and sets it so that it can be secured by pincers and drawn out without breaking; it is afterward led to a spool on which it is wound.

The second apparatus, which is more complete, contains a number of such glass tubes, and illustrates the method by which two or more filaments can be drawn

out and twisted so as to form one thread. The third machine is arranged for practical work. The dissolved collodion is contained in a copper receiver, having a capacity of about 15 liters. In this receiver it is subjected to a pressure of from 8 to 10 atmospheres that forces the liquid through a horizontal tube, to which are connected 72 capillary tubes, each with their surrounding water casings. In this manner 72 filaments of artificial silk are produced simultaneously, and these can be spun into threads of various thickness, three such filaments being twisted as a minimum and ten as a maximum. To effect this there is placed parallel to the horizontal tube a rack carrying a series of bronze blades that serve to guide the filaments; the twisted threads are wound upon bobbins running on spindles mounted parallel to the horizontal tube. A frame carrying as many pincers as there are capillary tubes can be put in movement by means of a cord, and if any of the threads are broken these pincers take hold of the filament and join up the broken parts. This apparatus is inclosed in a hermetically sealed glass case, through which a current of air is continually forced by means of a fan. This air is warmed to assist in drying the filaments; but it becomes cool at the exit and deposits the vapors of ether and alcohol.

The circulating water, which is employed to harden the filaments, is discharged into a receiver. It contains a large percentage of the volatile products which can be recovered by distillation, and in this way only about 20 per cent of the ether and 10 per cent of the alcohol are lost. One tube can produce from 3 dwt. to 5 dwt. of filaments per hour, or a length of nearly 1¼ miles. The apparatus works continuously, and with but little attention, and if by any chance one of the capillary openings becomes sealed, it can be cleared by applying heat. Under the conditions in which the machine is exhibited at work, the artificial silk can be sold at from 15 fr. to 20 fr. the kilo., while real silk cost from 45 fr. to 120 fr. the kilo. The manufactured product resembles very closely the natural one, it is smooth and brilliant, and the filament has a strength about two-thirds that of silk. Woven into a tissue it appears stronger and less liable to cut, this property being due to the fact that it is not charged with destructive materials which appear to be always used in dyeing silk, such as zinc or lead. These foreign matters are probably introduced solely for the purpose of weighting the silk; but there is no object for similar adulteration of the artificial product, because the metallic preparations employed cost as much as the collodion thread.

According to M. De Chardonnet, the density of his product lies between that of raw and finished silk. Its resistance to a tensile strain varies from 15 tons to 23 tons per square inch. (Copper breaks under a load of about 18 tons, and iron under 23 tons.) The elasticity is about the same as that of natural silk, and the inventor claims that it has a superior brilliancy. M. De Chardonnet exhibits a number of stuffs woven wholly with the artificial silk, as well as others mixed with natural silk and other textile materials. The results are really very remarkable. Among other objects, he shows a chasuble of artificial silk, which will bear very close examination.

Artificial silk is not yet manufactured on an industrial scale, but it appears that this will very shortly be done, and while it is impossible to foretell with certainty what will be the commercial results of this curious invention, it is impossible to resist the conclusion that it is highly practicable, and that it even contains the elements of great future success.—*Engineering*.

Important Patent Cases Decided.

Two important decisions were lately rendered by Judge Wallace, in the United States Circuit Court. The first was in the famous paper bag patent controversy, involving the right to the patent for the square-bottom paper bags. The Union Paper Bag Company and James M. Waterbury were the litigants, and Judge Wallace decided against Mr. Waterbury. The right to this patent is estimated as next in importance to that of the telephone, and involves over a million of dollars. George Harding and F. F. Chambers represented the plaintiff, and F. H. Betts and A. H. Walker the defendant.

The other decision was against the Third avenue surface road for using the patent of Henry Root for a cable grip without compensation to the patentee. Judge Wallace granted a permanent injunction to Root, restraining the company from using the grip. Frost & Coe were the company's attorneys, and George Harding represented the plaintiff.

Work of Electricity.

There are now in use in the United States more than 5,650 central electric stations for light and power. There are 210,000 arc lights and 2,600,000 incandescent lamps. There were fifty-nine electrical railways in operation in March last, and eighty-six roads in process of construction. The increase of capital in electrical investments during 1888 was nearly \$70,000,000. These are very significant figures, and they point unmistakably to the course of future inventions and discoveries.

THE PALACE OF FOOD PRODUCTS AT THE FRENCH EXHIBITION.

Up to the present, in universal exhibitions or those of less importance, food products have been relegated to unoccupied corners, or placed under tents put up in haste in ephemeral board structures having no pretensions to magnificence.

In 1889 this is all changed. The managers of the exposition, with a true appreciation of the influence that alimentation has upon a people, from a physical as well as an intellectual and a hygienic as well as a moral standpoint, have accorded the *animal* the place that belongs to it.

The fine arts have a palace on the Champ de Mars; and food products, too, have theirs—a true palace, vast, sumptuous, and monumental. The architect in charge of the work, Mr. Baubin, whose unaffected modesty shuns renown and applause, and who, moreover, is one of the most distinguished of his profession, has striven to scatter the "gold dust of his talent" over the work confided to him, and gastronomy will not have to be jealous of its grave neighbors.

The facade of the Gargantua Hotel is charming in its simplicity. Almost on a level with the water, in the base-


Natural History Notes.

The Larva of the Common Tiger Beetle.—For agility, strength, and ferocity, this larva is a veritable tiger among the insect world. Its body is long and narrow when young, but becomes broader as the larva approaches the pupa state. After each moult its color is a soft creamy white, which in a few hours changes to a dead black, except in the creases and under parts, which remain lighter. When hungry, it is lithe, active, and quick-motioned, jerking, twisting, and throwing its tail up over its back when molested. Its strong jaws, too, are ever as ready to be used in its defense as in procuring food. The specimens observed by me seem to prefer cutworms as an article of diet, the common garden worm being usually chosen. The tiger larva seizes the worm near its head as it lies in its underground retreat. The struggles of the doomed worm—often several times larger than its assailant—throw both combatants to the surface of the ground, where it continues in the vain effort to free itself until it can struggle no longer, the bloodthirsty little tiger burying its jaws deeper and deeper into its victim, until sometimes its whole head and fore legs are hidden. Without loosening its hold it continues to drain the

laid their eggs on him and the myriads of tiny maggots that hatched out of these eggs burrowed into him and literally ate him alive—a cruel ending to a cruel life. When nothing was left of him but a shell, and a very thin shell at that, the maggots pupated, and shortly after came forth tiny, innocent-looking flies, to act over the same tragical drama. Well, such is (insect) life! In the midst of prosperity comes adversity, and *vice versa*.
WALTER A. LYNN.

The American Catalogue.

The United States Commission have earned the distinction, says *Engineering*, of being the last country of importance to publish a catalogue. Although it appears thus tardily it is a very creditable production, being issued as a bound volume of about 250 pages. The map that accompanies the volume has been copied from that issued with the British catalogue. Probably a feeling of delicacy on the part of the American compiler made him hesitate to acknowledge the source, for it is such a very badly executed copy. Nearly 2,000 names of exhibitors are recorded in the index, a large result as to quantity, but somewhat misleading, as a



THE FRENCH EXHIBITION—THE PALACE OF ALIMENTARY PRODUCTS.

ment, are seen wines placed in lines in a hall that preserves the coolness of a cellar. On the first floor, facing the Seine, and on the ground floor of the quay side, extend spacious galleries, in which are brought together all the food products of the world. Three halls, one in the center and two in the wings, are glazed from the flooring up, and are surmounted with cornices in the form of angular frontons that intersect the long line of the entablature. The central *motif* is flanked by two very original turrets, which terminate in open-work belvederes whose elegant outline is coquettishly reflected in the river.

Wooden balconies here and there perforate the wall against which the sashes rest within. The entire sculptural decoration, in the gutter, the frieze, the jamb linings, the brackets, and the pilasters, recall the divinity of this cathedral erected to gluttony.—*L'Illustration*.

Pasteur's Method for Rabies.

Before the Academy of Sciences a paper was lately read by M. L. Pasteur on the prophylactic method as applied to patients after being bitten. In his brief report for the year ending May 1, 1889, the director of the Pasteur Institute announces the treatment of 1,673 subjects, of whom 6 were seized with rabies during and 4 within a fortnight after the process. But 3 only succumbed after the treatment had been completely carried out, making 1 death in 554, or, including all the cases, 1 in 129.

worm until it is gorged and the worm a mere shell, when it leaves what remains of its victim and retires under the damp earth, where it remains inactive until ready to moult.

In one experiment three tiger beetle larvæ, two of them over half an inch long and the other much smaller, were placed in an insect cage containing thirteen cutworms. In two days only three of the worms were left in company with the two larger tigers, the smaller and the ten worms having been killed and devoured by the larger two. The worms were not, however, so completely drained as those I had observed before. Probably the larvæ had selected the choicest parts on account of the plentiful supply. They had visibly increased in size, but not to the extent one might suppose after having had such a feast. The supply of cutworms running short, the stronger larva did not allow his brotherly regard to interfere with his appetite, but fell upon and devoured his weaker companion. I kept him two weeks, during which he ate seventeen worms, nearly all of them larger than himself.

But a fate more terrible than that of the cutworms overtook him at last. He became dormant and prepared to go into the pupal state. For a day or so I had noticed many very small flies around his cage, but did not think of parasites, which was just what these small flies were. The tiger larva shed his larval skin, and while he was in this condition, soft and utterly helpless, the parasites attacked him. The little flies had

pears on analysis. In the groups devoted to works of art there are 255 exhibitors, and some highly creditable pictures have been contributed. Thanks chiefly to Mr. Pickering's efforts the collection in the Machinery Hall is a very high class one, but the Industrial Court appears to be a great disappointment to Americans themselves. At least 700 exhibitors are found in those classes devoted to education, books, printing, etc., and nearly all the objects shown are either current numbers of periodicals, reports or catalogues of publications or of institutions. Current numbers of the *California Cackler*, the catalogue of books in the Young Men's Christian Association library at Meriden, Conn., the file of the *Swarthmore Phoenix*, and even Betsy Ann White's *Three Holes in a Chimney* have more of a local than an international interest, and do not tend to elevate the standard of excellence.

Our contemporary might have added the above forms part of the fun to pay for which Congress appropriated two hundred and fifty thousand dollars cash from the treasury.

Hot Decks in Torpedo Boats.

The steel torpedo boat D lately arrived at Calcutta from England, but it is to be feared one great drawback to her general utility will be her iron or steel decks, which radiate heat copiously. Her chief officer was landed at Kidderpur ill with sunstroke. A few iron decks are coated with India rubber, but it is a poor heat insulator.

SODOM DAM AND RESERVOIR.

BY HAROLD BROWN, C.E., HYDRAULIC ENGINEER.

An examination of the broken Conemaugh dam by a committee of expert engineers, has revealed an earth-work construction which, to all intents, was equal to the duty expected of it as a mere resistance to the quiescent pressure of the impounded waters. Their report has not yet been made, and in the meantime the general public through its spokesman, the newspaper press, has discussed the construction of dams, particularly earthen dams, in terms more forcible and terse than technical, and weighted with much misunderstanding.

Most hydraulic engineers are agreed as to the safety and durability of good earth, homogeneous throughout and properly constructed. The best kind of an earth dam is that which is made of hard compacted gravel with sufficient clayey matter to bind the whole together, coated by puddled clay bands or layers to prevent percolation, and protected on the exposed upstream and down-stream faces by paving, with sufficient slope and thickness to withstand quiescent pressure and wash of rain storms, and high enough above the flow line to exceed the greatest flood known to the locality.

Sometimes the center core of such a dam is a puddled wall, that is, a layer of clay upon clay and gravel, rolled and rammed section after section until the whole is firmly compacted together, and high enough for the duty it is to perform; this forms a tough, elastic mass, impervious to water, possessed of great weight, and when protected from flowing water capable of resistance to a great pressure. It is generally covered by a more porous material, which in its turn is protected by paving blocks laid dry.

One writer of authority says that the cheapest and poorest type of this kind of work is a stone wall 2 to 3 feet thick, with an embankment on each side of it. Such a wall adds nothing to the stability of a dam, but is rather a detriment. Its function is merely to arrest percolation of water and prevent penetration of vermin.

The public is not generally aware that our city authorities are now building a dam that is in some respects similar to a type of dam which is not wholly approved by the best engineering authorities.

In the annexed cut is shown a plan of the east branch reservoir and its connecting tunnel. According to the specifications, Sodom dam is to be built on the east branch of Croton River, to consist of a masonry dam (see section) presenting at its deepest part a height of about 78 feet (exclusive of the foundation below the river-bed), a width at base of about 47 feet, and a total length of about 500 feet with a uniform thickness at the top of about 12 feet. A gate house is also to be constructed of masonry, a pipe vault and fountains, with all the connecting pipes, a masonry overflow connected with the masonry dam by an earth embankment, which is to contain a center wall of masonry, a spillway and river walls, and all work necessary to take care of the river water during construction.

The object of the dam is to impound the waters collected by its tributary watershed for storage purposes. The work that is now going forward is of a twofold character, consisting of two dams and two reservoirs, one called Sodom dam reservoir, and Bog Brook reservoir. The storage capacity of Sodom dam and Bog Brook reservoir is estimated at 9,000,000,000 gallons. The two reservoirs are to be connected by a tunnel aqueduct, the approaches are to be made in earth and rock excavation, and are to be finished in masonry. The tunnel is to be lined with brick, and

Our drawing shows the plan and location of both reservoirs, with Sodom dam and the connecting tunnel.

The north portal of the tunnel is shown in the annexed cut.

It will be observed, upon an inspection of the plan of the dam and its spillway, that advantage has been



MAP OF CROTON RESERVOIRS.

taken of a piece of high ground to locate the spillway upon a course almost parallel to the general course of the river. This necessitates the overflow moving around a salient angle, the union between the spillway bank and the masonry being made by a natural rise of ground forming a frustum of a cone, which is nearly 200 feet wide on top.

The masonry dam seems to be admirably adapted to its purpose. A roadway 12 feet wide runs along its crest the entire length, and also along the top of the spillway embankment. This embankment is described briefly as follows:

After the soil has been removed from the ground forming the base of the embankments, it is grubbed and cleared of all stumps and other perishable matter, and if the material under the soil is not of satisfactory quality, it is to be removed and replaced by other material. By soiling is meant the surface ground, that is the natural sod, or brush or undergrowth, the first layers of loose earth containing roots of grasses or other organic growths. The earth used for the embankments is to be free from stones larger than 3 inches in diameter. All perishable matter to be excluded. The embankments are to be formed in horizontal layers not more than six inches in thickness, thoroughly rolled with heavy grooved rollers wherever practicable, and rammed by hand where the roller cannot reach. Each layer is copiously watered, so that the layers may be kneaded or puddled together. An extra width of twelve inches is to be provided on the slopes, and the surface left is to be dressed smoothly to receive the broken stones that are strewn thickly about to support the final surfacing of paving. The thickness of the paving in the spillway and in the slope walls of the embankment is to be eighteen inches. Each stone will be set solid on the foundation of broken stone or earth, without allowing any interstices. In the river walls large stones are to be used, especially

for the face, the walls to be bonded with frequent headers, that is stones running with their longest axes transversely in the wall. Riprap, or large heavy stone loosely piled, may be used in some portions of the work wherever it would not be detrimental to the embankment behind it. After the slopes which are to receive the slope walls have been dressed, a layer, twelve inches thick, of broken stones, is to be spread as a foundation for the paving. The stones used will be two inches or less in their greatest diameter.

Rubble stone masonry is to be used for the side walls of the overflow spillway, for the weir of the overflow and adjoining parts, and for the center wall of the main embankment. This center wall at its greatest width is to be 6 feet through, and at the top 5 feet; this wall is shown in our cross section of the earth embankment of the spillway wall.

This embankment with its wall core of masonry extends some 760 feet in a direct line, at the extreme base about 115 feet in width, with a slope of 2 to 1. If there is any point in the construction that is open to a difference of views and that is likely to be misunderstood, it will be found at this point.


One of our ablest engineers says that whether a given dam should be constructed of earth or masonry will be determined, except for considerations of cost, by the character of the foundation and the available material. If the dam has to rest upon earth, then it should be constructed of that material, unless for some very exceptional reason, as it is much easier to make an impervious union between earth and earth, or between masonry and rock, than between masonry and earth. This will be especially true if the rock foundation does not extend all the way across or up the sides of the valley, as to carry masonry from a rock to an earth foundation without incurring rupture at the point of change is an exceedingly difficult and delicate matter.

If possible, a heart wall of puddle or masonry, as tending, by its lack of homogeneity, to produce unequal settlement and consequent longitudinal cracks, which, by serving to connect partial transverse ones, may lead to more or less serious leakage and possible rupture. Another danger attending the use of a heart wall is that in case the dam is overflowed, the heart wall may prevent the crest from being materially lowered until the back slope is nearly or quite washed away, when the heart wall and the portion of the inner slope supported by it would be liable to give way suddenly and let out with a rush a large portion of the contents of the reservoir at once.

A gravelly clay is the best material for puddle, as, while the clay furnishes the water tightness, the gravel reduces the settlement, and increases the resistance of the clay to washing.


The crest of the spillway is ten feet below the crest of the dam, and accords with the best practice. It is proportioned to carry off the maximum storm flow with a depth of five feet of water, so that the water should never be less than five feet below the crest of the dam.

In the first place, the conclusions from the foregoing premises are arrived at from a long and careful study of the action of water upon impounding structures. In the Sodom dam, the essential resistance of the main body of the storage is met by a masonry wall or curtain which will be described more fully. Advantage is taken of the high ground to locate a waste weir or spillway at one side. The water washes over a well paved embankment, and it is not a question of a direct resistance to a deep body of water that is met by the spillway embankment, but a shallow body of water with a certain ratio of movement. In the direct action of this flow there is a scouring action exerted on the inner face of the embankment, and if the



SODOM DAM-DETAILS.

the space between the extrados of the tunnel arch and the line of excavation is to be filled with suitable material, generally dry rock filling or rubble masonry, according to the nature of the material excavated and the character of the rock roof. The tunnel aqueduct is to be circular in section, about 10 feet in diameter,



SODOM AND BOG BROOK RESERVOIR DAM.

embankment were undermined, it would come from the dynamic rather than static action of the water. In the case of a great flood such action would be positive to a large extent, and to what extent would depend upon the amount of water and the rapidity of its flow. From the direction in which the main body of the water to

the spillway runs, it does not seem possible to overthrow the embankment by static action.

In regard to a matter of detail, the heart wall would be of greater service than it now is in holding the embankment together if it were counterforted on both outer and inner face at intervals of 10 or 15 feet, stepping back from bottom to top, for then whatever unit of resistance the wall obtained as a wall would be added to the inertia of the embankment. It will be observed by our cross section that a homogeneous union between the wall and its foundation has been achieved by excavating a bed in the rock upon which to begin the first courses of the heart wall. This is a wise precaution; there is not much evidence, however, of a close union of the earthwork with the masonry core, as the heart wall is battered on both outer and inner face and no rough projections are left for the earthwork to cling to, to increase its own measure of resistance.

The overflow crest is 500 feet in length, and calculations based upon the data of rainfall for this watershed would indicate that length to be sufficient. This is of great importance when it is remembered that in the opinion of some of our most eminent engineers, Conemaugh dam would not have "gone down" had the overflow weir been sufficient to carry off the flood excess.

As to whether the spillway embankment should have been constructed of earth alone, or with a heart wall, there is room for a difference of opinion. From the wording of the specification in regard to this construction, it would appear that the engineers apprehended no lack of good material, for the material necessary to the making of the embankments is to be taken from the wall trenches, from the spillway below the overflow, and from any place within 500 feet of the point where it is to be deposited.

The masonry dam is to be built of sound quarry stone, roughly rectangular, with all irregular and feather edges hammered off. Their beds must be good and present such even surfaces that, when lowering a stone on the level surface prepared to receive it, there can be no doubt that the mortar will fill all spaces. The largest stones are not to measure more than 20 cubic feet, and they are to be used in the proportion of 25 per cent of the whole at most, but they may be omitted partially or entirely if their beds are not satisfactory.

In the annexed cut is shown a sketch of the work now in progress on the masonry dam. The larger stone is loaded on a carrier or trolley, hoisted up to clear the wall, and carried on a 2 inch wire rope and lowered to whatever position desired. The point of view is from the down-stream side of the dam. At the center are shown the outlet pipes that supply the fountains; directly opposite, on the inner face of the dam, the gate house is situated. Its object is to take the water from the lake, where it is received in great masonry chambers and distributed by underground pipes to the fountains. The gate house is developed into a tower which provides a living room for the keeper and a point at which the daily height of the water can be measured and a constant oversight of the entire work be maintained.

The fountains are seven in number, and are an especial feature of this work. From a landscapist's point of view, they will form an attractive center about which is grouped the imposing wall of masonry, with its interesting driveway, the long stretch of swarded bank on the spillway, and the overflow curtain of water making murmurous rhythm to the cadence of the splashing waters of the fountains. While the effect will be of a pleasing character and enlist the admiration of the public, it will also be recognized as essential from a wholly utilitarian point of view. The water passing through the fountains will be thoroughly aerated in its fall to join the waters of the overflow, and whenever needed from this source it will not be stagnant, but living water. Our view of the scene will enable the reader to get a better image of the group of fountains and their surroundings than any word painting can convey.

As shown in our sketch, the masonry of the dam is to be laid on its outer faces in ranged courses. Each course is to be composed of two stretchers and one header alternately, the stretchers not to be less than 3 feet long nor more than 7 feet long, and the headers of each successive course are to alternate approximately in vertical position. The rise of the courses is to vary from bottom to top from 30 inches to 15 inches in approximate vertical progression, and the width of the bed of stretchers is not to be at any point less than 28 inches. The headers are to be not less than 4 feet in length. The face joints are to be pointed with pure Portland cement after the whole structure is completed.

The specifications provide for an optional layer of brickwork on the inner face of the dam. In this work the bricks will be heated to a certain temperature, the mortar to be made of a mixture of Trinidad asphaltum and plaster of Paris. From various experiments which have been made with asphaltum mortars in France, and the results of the examination of asphaltum joints in the remains of Nineveh, there is every reason to

believe that a mortar made of rock asphaltum would be more homogeneous and impervious to water than a mixture of plaster of Paris with asphaltum. The shrinkage and expansion of the plaster depends so largely upon the manner of its tempering, and asphaltum is of such an utterly different character, that the union of the two will require more skill than ordinarily falls to the lot of workmen in the construction of dams. It would also appear, from our present knowledge of cements, that to point a wall with pure neat cement when the beds and joints are laid in cement mortar is open to exception; while neat cement alone possesses greater imperviousness than cement with sand, the question of complete adhesion to the stone-work and the mortar behind it is of equally vital importance, and there is no doubt of a better joint and surface with a small amount of sand added to the cement than with neat cement alone. These questions of detail have no doubt been carefully considered, and what has seemed best under the circumstances has been adopted. The belief is growing stronger among our engineers that a more frequent use should be made of asphaltum mortar. When properly made and tempered, it is superior in every way for any purpose to lime mortar. Water seems to exert upon it no appreciable solvent action.

While the Sodom dam is one of the minor constructions in the congeries of works that constitute our new system of water supply, and its function is essentially subordinate as a storage basin, there can be no doubt from a study of the many detail drawings which have been carefully made, and the clauses in the specifications which explain these drawings and provide for their proper execution, that it has received an amount of study and research second to no important work ever undertaken for the public.

Radiating Power of Flames.

At a recent meeting of the Berlin Physical Society, Dr. R. Von Helmholtz communicated the results of his experiments on the radiating power of flames. The problem which he had set before himself was to determine the relationship between the radiant energy of flames and the amount of gas consumed for their production. The latter was measured by the fall of the gasometer globe which contained the gas, the former by means of a bolometer, for each of whose scale divisions the equivalent value in heat units had been carefully determined by three different methods. The radiating energy of the flames depended upon a number of conditions which were each severally investigated; as, for instance, the size and shape of the flames, the amount of foreign gases introduced, and the ratio of the amount of oxygen to the amount of gases with which it was mixed. For the purposes of comparative measurements, a moderately high flame was chosen, which produced no smoke and was 6 mm. thick. Luminous flames radiated more energy than non-luminous, and it was proved by an extended series of careful quantitative experiments that the radiating power of the flames was not dependent upon their temperature. From this it follows that Kirchhoff's law does not hold good for flames—a result which is, however, quite in accordance with the limitations he put to his law for those cases in which heat is directly converted into radiating energy. In the case of flames it must be borne in mind that chemical affinity comes additionally into play; the speaker entered fully into the influence of this upon the radiation of energy, and endeavored to make it clear by means of an extremely interesting hypothesis. After this he stated the numerical data which he had obtained for both luminous and non-luminous flames, produced with a series of gases—hydrogen, carbonic oxide, methane, coal gas, methyl alcohol, etc. Starting as a basis with Julius' statement that the products of combustion are the only criteria of the amount of radiation, and hence calculating the radiating energy of the flames, he obtained values which corresponded very closely in most cases with those actually observed. Finally he calculated the total useful effect which can be obtained as radiant energy from the gases which are being consumed in the production of the flame. From this he arrived at the interesting result that it is far more economical to use the gases for driving a dynamo which supplies incandescent lamps, and to utilize the energy radiated from the latter, than to burn the gases and utilize the energy which is radiated out from their non-luminous flames.

Height of Great Sea Waves.

Carefully repeated experiments made by an experienced English navigator at Santander, on the north coast of Spain, showed the crest of the sea waves in a prolonged and heavy gale of wind to be 42 feet high; and allowing the same for the depth between the waves, would make a height 84 feet from crest to base. The length from crest to crest was found to be 386 feet. Other estimates of the waves in the South Atlantic during great storms give a height of 50 feet for the crests and 400 feet for length. In the North Sea the height of crest seldom exceeds 10 feet and the length 150 feet.

A New Fire-Proof Non-Conductor for Pipe and Boiler Coverings, etc.

In all non-conductors, the endeavor is to provide as large a number of air cells within a given space as possible, in a material that is itself very light, such materials having been found by experience to best confine the heat. The lightness, porosity, and elasticity of the common sponge, composed as it is of fine flexible, tenacious fibers, interwoven in the form of cells and meshes, constitute the ideal structural qualities for a perfect non-conductor. Taking advantage of this fact, Mr. H. W. Johns, of New York, has succeeded in perfecting a new article of manufacture styled asbesto-sponge, which has been patented in this country and Europe, and has been but recently put on the market by the H. W. Johns Manufacturing Co., in various practical forms, as a non-conductor, notably as a covering for steam pipes and boilers.

The tentacle-like barbs of the sponge, as prepared in the manufacture, are so intertwined with the fine, silky fibers of the asbestos as to make a material at once very elastic and highly porous, while at the same time it is so light that a barrel of it, in the form of filling, barely weighs fifty pounds. And this, too, is effected with the use of so small a percentage of sponge that the material is practically fire-proof. A sample of this filling which was in practical use for several months as a covering for a steam pipe, in which a pressure of 100 lb. was constantly carried, on being taken off and examined showed the same vitality and "spring" which it had when put in place, the sponge portion of the compound not being at all affected, while, of course, it was impossible for the heat to touch the asbestos.

This new material has double the bulk or covering capacity of the same weight of hair felt, and more than three times that of pure asbestos, making its cost, as stated, less than that of any other material employed for similar purposes. It is also supplied in the form of an asbesto-sponge felt and an asbesto-sponge lined felt, furnished in rolls of varying thickness, as well as in an asbesto-sponge cement felting. This latter composition partakes of the nature of a felt and a cement, and is put up dry in barrels to be mixed with water to the consistency of mortar, for applying to steam pipes, boilers, etc., while heated; also coming extensively into use for covering locomotive boilers.

In the manufacture of fireproof asbestos cloth for theater curtains, mittens, aprons, masks, etc., the H. W. Johns Manufacturing Company has produced goods which have stood the severest tests and proved their efficiency in many emergencies. A case in point was afforded by the recent blowing off of the cap of a tube in a gas well in Canada, it being impossible to extinguish the flame or get near the tube for several days. It was estimated that eleven million feet of gas were being burned every twenty-four hours. The noise from the flame and the danger attending it caused no little excitement, and \$1,000 was offered to any one who would extinguish it, which was finally accomplished by a man dressed in asbestos cloth and wearing a cone-shaped mask of the same material. Curtains made of this cloth are now in use in many of the large opera houses and theaters of the country, as a fire-proof barrier between the stage and the auditorium.

The asbestos building felt made by this company has long been well known, and its good qualities are highly appreciated by all of the best builders and architects. This felt was used throughout for floor linings and in partitions in the fine buildings of the Pratt Institute in Brooklyn, and several tons of it have been used in the new Roman Catholic asylum now approaching completion in Manhattanville. It is composed entirely of asbestos, this being absolutely fire-proof, and will not disintegrate by age, is odorless and vermin-proof. It is largely used for lining weather boards, shingle roofs, etc., and is put up in rolls of different thicknesses.

Of all articles of any considerable use that are composed wholly or in part of asbestos, Mr. Johns has long been recognized as the pioneer inventor as well as the most successful manufacturer. He commenced work in this field in 1858, and has since then given his unremitting attention to perfecting and introducing asbestos products wherever such materials could be made useful for structural and mechanical purposes. He now owns and controls upward of one hundred patents on the manipulation and uses of asbestos, many of the goods so made, and now having large sale, having been brought forward as new articles of manufacture. Mr. Johns exercises a controlling interest in the business of the H. W. Johns Manufacturing Company in New York and Brooklyn, a business which has steadily increased in volume, year by year, with the new uses and wider fields which have been found for asbestos materials.

THE *Annals of Hygiene* has discovered there is nothing that so quickly restores tone to exhausted nerves and strength to a weary body as a bath containing an ounce of aqua ammonia to each pail of water. It makes the flesh firm and smooth as marble, and renders the body pure and free from all odor.

A Criticism of Pasteur's Method.

Dr. Joseph Drzewiecki, physician to the University Clinic at Warsaw, has sent us a paper in which it is contended that the method of anti-rabic inoculation for the prevention of hydrophobia is unscientific. He claims that M. Pasteur has never given a satisfactory answer to the objections urged by Frisch, Ullman, and Peter; and he revives the arguments used by M. Luteaud in the *Journal de Medecine*, which were based on the statistics adduced by Pasteur. He points out that, although the English commission investigated 90 cases, in only 24 of these were the bites inflicted by undoubtedly rabid dogs, so that the number of 8 fatal cases was far in excess of the usual proportion of 5 per cent. Further, that, although according to the report of that commission the total mortality among the 2,682 cases treated by M. Pasteur would ordinarily have been 130 instead of the 40 actually recorded, it should have been stated that only 233 cases were bitten by rabid animals, and that therefore the estimated mortality ought to have been only 15. Both M. Luteaud and M. Peter argued that the Pasteurian method had increased the rate of mortality. The statistics of Dr. Kischensky are then quoted. They were obtained from the archives of the Katharine Hospital at Moscow. From them it appears that, of 307 persons bitten by unquestionably rabid dogs, 18 were bitten in the head (4 deaths), 90 were bitten on the hands (2 deaths), 25 on the feet (no death), and of 170 bitten through the clothes only 1 died. To these may be added 1 fatal case among 4 in whom the site of the bite is not recorded. This gives a total mortality of 2.6 per cent. The mortality among those bitten by rabid wolves (24 cases) was 30 per cent; according to M. Pasteur, it should be 82 per cent. In all the fatal cases the bites were very extensive, and on the head. Of 17 cases bitten by rabid horses, 9 were admitted within three months, but none developed hydrophobia, 1 died from erysipelas and 1 from septicæmia. Of 4 bitten by a rabid hog, none fell ill; there were 4 cases bitten by rabid men, 1 by a white bear, and 1 by a rabid squirrel. Thus, of the total number (396) bitten by rabid animals, 18 died, or 4.52 per cent. Dr. Drzewiecki maintains that Pasteurian inoculation does not prevent hydrophobia in man, and that M. Pasteur only proved that it prevents rabies in the dog, which, however, was not even borne out by the experiments of Frisch. The particulars of some of the fatal cases treated during last year at the Pasteur Institute are cited to support the contention of the inefficacy of the method; and the plea that severe cases of bites on the face or head cannot be successfully treated is held to show that the method is not truly anti-rabic. Again, if the inoculations modify the intensity of the virus, how is it that the symptoms exhibited by the fatal cases are so severe? The method, Dr. Drzewiecki thinks, may be of value to the veterinary surgeon, but applied to man "it is unscientific, and as such must be condemned in the interest of humanity and science."—*Lancet*.

How and When to Drink Water.

According to Dr. Leuf, when water is taken into the full or partly full stomach, it does not mingle with the food, as we are taught, but passes along quickly between the food and lesser curvature toward the pylorus, through which it passes into the intestines. The secretion of mucus by the lining membrane is constant, and during the night a considerable amount accumulates in the stomach; some of its liquid portion is absorbed, and that which remains is thick and tenacious. If food is taken into the stomach when in this condition it becomes coated with this mucus, and the secretion of the gastric juice and its action are delayed. These facts show the value of a goblet of water before breakfast. This washes out the tenacious mucus, and stimulates the gastric glands to secretion. In old and feeble persons water should not be taken cold, but it may be with great advantage taken warm or hot. This removal of the accumulated mucus from the stomach is probably one of the reasons why taking soup at the beginning of a meal has been found so beneficial.

Heart Failure.

"It would be an excellent idea," says the *Manchester Union*, "if physicians of the present day would invent some other reason for about all of the deaths which occur nowadays than the cheap fraud, 'heart failure.' This might not be of serious moment were it not for the fact that hundreds of people are being nearly frightened to death by the constant use of the cause for sudden deaths, and many people who are sick, and necessarily have some heart symptoms, are kept in constant terror by reading or hearing in other ways of death after death by heart failure. There are probably no more deaths from heart failure in these times than heretofore, but a new cause for death has been coined, and the nervous and timid are being severely injured by it." We would suggest that hereafter physicians use the term "cardiac asthenia," which has a learned sound and means just the same. The immediate cause of death in many diseases being, in fact, "heart failure," we do not see how otherwise the "nervous and timid" can be protected.

THE COCO DE MER—LODOICEA SEYCHELLARUM.

BY CHARLES D. BAKER.

On a map the Seychelles group of islands are represented by a dot not larger than a pin head, yet there are thirty of them, and one, Mahe, is eighteen miles long and from three to five miles broad. They lie nearly in the Indian Ocean and just south of the equator, 3° 40'–5° 35' S. lat. and 55° 15'–56° 0' E. long. These islands abound with interesting subjects to the student in natural science, but among them none is more wonderful or striking than that famous tree, the Coco de Mer. Nowhere else in the world can this tree be found except on the islands of this group. At one-time Curieuse and Praslin were covered with the trees, but travelers who have recently visited the islands say that the vegetable wonder has vanished from the first, but is plentiful on the second. One of these explorers was Col. Nicholas Pike, for seven years United States



THE COCO DE MER—LODOICEA SEYCHELLARUM.

consul at the island of Mauritius, which is nine hundred miles distant, and to which colony the Seychelles group belongs. In describing his impressions of the tree, he says: "The first appearance of the curious Coco de Mer is disappointing, and at a distance looks quite disreputable for so famous a tree. Imagine a tall thin stem towering up over a hundred feet, with a great ragged head of green and withered leaves. The impression is not favorable, a common cocoanut tree is handsomer. These, however, are the male trees; the females are rarely over 60 or 70 feet, and not being so high, are less exposed to the winds. When about twenty or twenty-five years old, before the stems begin to rise, it is certainly one of the loveliest productions of the vegetable world, and here it is seen in all its beauty."

The leaves of the Coco de Mer are winged and palmated, and when the stem is just rising above the ground, in favorable situations, they attain a length of fifteen feet exclusive of the petiole, which is of an equal length and 12 feet wide, but both diminish in size as the trunk increases in height. This is a necessity, as the tall thin stem could not support a head of such large leaves and the heavy fruit which the tree bears. Travelers often give the natives small sums of

money, for which they will climb the trees and swing upon the great leaves—a feat attended with much danger, considering the great height of the leaves from the ground.

Before the leaves unfold they are covered with a thick cottony substance, which is used for mattresses. When about thirty-five years old, the tree begins to blossom. After three years from fecundation, the fruit has attained its full size and is called *Coco tendre*. It can be cut with a knife in this stage, but gradually becomes hard and black, but it is seven or eight years from time of fecundation before it is ready to fall. The double nut, with the husk around it and when fully developed, is about the size of a bushel basket. The meat of the nut is agreeable eating, and tastes like the cream of charlotte russe. The shell of the nut is used by the natives for scoop buckets, and is put to a variety of other uses. These immense nuts used to be found floating in the Indian Ocean, and gave rise to any number of fabulous stories in regard to their origin. It was claimed by many that they grew in the sea, but this claim, of course, was easily refuted; but nevertheless, this peculiarity is kept in remembrance by the name which the tree bears, Coco de Mer, or cocoanut of the sea.

When the nut falls to the ground, the first act in the future tree's life is perhaps as wonderful as anything in its future history. It takes nine months after planting before the germ is ready to start, when it shoots out from the nut and creeps along the ground, drawing nutriment from the ground as it goes. When a distance of some twenty feet has been covered, it begins to shoot upward and to put forth leaves, each leaf requiring a year's elaboration in sun and air before the next appears. If the nut does not fall germ downward and meet the ground so as to draw substance from it, after an ineffectual struggle for some few feet on the surface all vitality is exhausted, and the vegetable baby dies from the heat of the sun and the lack of moisture. Another remarkable fact regarding the Coco de Mer is that it rests in a perforated bowl which in form resembles a colander. A great number of rootlets radiate from the trunk and run through the holes in the bowl and then extend into the earth, sometimes for thirty feet. When violent winds blow, as they frequently do in this region, the tree, being tall and slender, with a great bunch of very heavy leaves and nuts forming a great bouquet on its top, bends over until it seems as if it must fall, but rights itself again, its long roots seeming to act like elastics, which draw it back into position again.

On the island of Curieuse, where there are now no specimens of the Coco de Mer, many of the bowls in which the trees once rested are still found in perfect condition, showing the imperishable nature of the material of which they are composed.

The numerous uses to which the leaves of the Coco de Mer can be adapted has led to the wholesale destruction of trees. The Mahometans use them to weave into praying mats, and they regard them as having a special sanctity. These leaves are very beautiful in their unfurled state, their edges being of a delicate green and the laminae of a clear pale straw color. Beautiful fans, artificial flowers, hats, ladies' work baskets, and other articles are made from them.

The expanded leaves are also used for thatch, and when folded together and pinned with little skewers of bamboo will hold nearly a bushel of fruit. The petiole is used for palings and often for rafters, being strong and durable. The trunks are split and used for palisades and for boards for the ends of houses, and pieces are hollowed out and used for gutters. They are considered imperishable. It is the opinion of Col. Pike and other investigators that the Coco de Mer is a specimen of antediluvian flora.

The Boulak Museum, Cairo.

The magnificent collection of Egyptian antiquities at the Boulak Museum is now, it appears, in the greatest jeopardy, and, unless the European public raise their voices in protest, a scheme, which will probably prove the ruin of all the more perishable objects, will shortly be carried out. It has been decided by the Egyptian government to remove the collection from Boulak to the palace of Ghizeh.

The palace of Ghizeh is totally unfit for the purposes of a museum. It is one of the numerous palaces built by the Khedive Ismail in the heyday of his extravagance, and, though it must have cost a very large sum of money, it is already in a dilapidated condition. The roof was never properly finished, and admits the rain in every direction, the floors and walls are unsound, and quite incapable of supporting the weight of the collection and of visitors, the lath and plaster cornices and ceilings are cracked and falling to pieces, and no amount of money can render it a suitable building for the exhibition of the objects of art proposed to be placed in it.

Persons contemplating building will find it to their advantage to subscribe for the Architects and Builders Edition of the "Scientific American." \$2.50 a year. Single copies 25c.

RECENTLY PATENTED INVENTIONS.

Mechanical.

SPRING MOTOR.—Ludwig Melchior and George Haas, Wilmington, Del. In a suitable framing is a gear train having a power shaft, spring arms being secured at one end to the framing and extended down on opposite sides of the gear train, while there are cords or connections between the free ends of the spring arms and the power shaft, and guides for the cords, the spring arms being multiplied as desired to increase the power.

MOTOR.—Evander B. Newcomb, Parsons, Kansas. In a suitably constructed frame is a transverse shaft, to which is secured one end of a coiled spring fastened by its outer end to the inside of a barrel mounted to rotate loosely on the shaft, the device being simple and durable, and especially designed to operate light machinery, such as sewing machines, jewelers' lathes, churns, etc.

CIRCULAR KNITTING MACHINE.—Charles E. Bean, Scranton, Pa. This invention covers a machine for controlling a plurality of threads or yarns of different colors, and constructed to automatically supply the different yarns to the needles in a manner to form any desired pattern, in stripes or other styles, in the knitted web, the machine involving a novel construction, combination, and arrangement of parts.

PLUMBERS' SAW.—Robert and Charles McAlpine, Trenton, N. J. This is a saw in which a reciprocating saw blade is held to the stock by an adjustable stop for regulating the extent of movement of the blade beyond the stock, with other special features, whereby pipe connections may be severed quickly and accurately within the narrow space usually available for such work in a plumber's trade.

Electrical.

PUBLIC CLOCK.—Alfred Speer, Passaic, N. J. This is a clock with large dial and mechanism for driving the hands by power applied to their outer extremities, to overcome the resistance of wind, ice, snow, etc., the mechanism being electrically operated by a step by step movement through pawl and ratchet devices acting upon pinions meshing into stationary circular racks.

Agricultural.

CORN OR SORGHUM HARVESTER.—Joseph J. Singley, El Dorado, Kansas. This is a machine to be drawn along the ground when the stalks are guided by adjustable fingers to be cut by the knife and fall upon the bed of the machine, the knife being detachably held between the lower finger and bed, and the stalks being conveniently delivered to the ground at any time when the desired quantity has been cut.

Miscellaneous.

PIPE COUPLING.—William M. Brown, Jr., Sacramento, Cal. This coupling is formed with hollow sections secured to the main steam supply pipes, preferably by a shouldered, end projecting into the main pipe, and held by ring clamps having their ends riveted together, being intended mainly for use with railway passenger cars, being adapted for automatic coupling and ready uncoupling.

CAN FILLING MACHINE.—Francis M. Nichols, Chillicothe, Ohio. This machine has a measure carrier with disks, each having tubes or cylinders open at both ends, the tubes of one disk sliding within those of the other, the apparatus providing means for filling cans with measured quantities of corn, tomatoes, etc., the cans being automatically fed forward to receive their intended contents.

TESTING DEVICE FOR COUNTING MECHANISMS.—Paul C. Ilgen, Leipsic, Saxony, Germany. Numbered counting disks are operated by a rotating shaft, in connection with a supplementary disk, whereby the accuracy of the number shown on the counting disks may be determined, when, if the figures do not agree, the counting mechanism is proved to be out of order.

REFUSE EJECTOR.—John S. Wallace, Nelsonville, Ohio. This device is specially designed to remove refuse from ocean steamers, coal mines, etc., and consists of a discharge pipe into which projects a steam pipe carrying superheated steam, a refuse feed pipe discharging into the discharge pipe, and a gas pipe also opening therein, by means of which the smoke and gases from the furnace combine with the superheated steam.

PURIFYING IRON.—Nathaniel Booth, Hollidaysburg, Pa. This invention covers a compound for purifying iron in blast and puddling furnaces, the compound consisting of red prussiate of potash, bichromate of potash, bicarbonate of soda, black oxide of manganese, etc., in stated proportions, being designed to eliminate phosphorus, silicon, sulphur, etc., from the metal, and especially applicable to red-short iron, reducing its crystalline character to a fibrous condition.

DOUBLE SULPHATE OF ANTIMONY.—Carl J. E. De Haen, List, near Hanover, Prussia, Germany. This is a process of manufacturing the double salt of fluoride of antimony, consisting in mixing fluoride of antimony and sulphate of ammonia and then evaporating the mixture, for the industrial application of the compound in the dyeing art in lieu of the more expensive tartar emetic.

CRACKER CUTTING DIE.—Carl Herrmann, New York City. This is a die provided with a face built up of removable sections which may be easily renewed when broken by an ordinary workman, and the die may be quickly repaired or partially refaced should it be broken by contact with hard substances in the dough or otherwise.

BICYCLE.—Louis A. Hill, Philadelphia, Pa. This invention relates to spring forks to be used in connection with the wheels of a bicycle or similar

machine, and provides means whereby the jolting motion of the wheels when passing over obstructions or a rough road will not be communicated to the rider or to the steering arms or handles.

COVER FOR MILK CANS.—Joseph C. Vail, Maple's Mill, Ill. This cover is made of an upper plate and an under apertured plate separated from the upper plate by spacing strips, the space between the two plates being ventilated, thus providing for the ventilation of the vessel while excluding dust, insects, etc.

KALEIDOSCOPE.—Joseph W. Lovibund, Salisbury, Wilts County, England. In this device, instead of the usual irregularly shaped and variously colored pieces of glass, disks are employed, independently movable by a rolling motion in the field of view, to separately or conjointly produce designs of great variety, which may be infinitely varied and repeated or reproduced at will.

TOY RACE TRACK.—William N. McManus, New York City. In this toy track a real race is simulated by a number of miniature figures carried about a circular race course, and after a number of times round the figures are projected forward by an impulse to the finish line, the invention being an improvement on a former patented invention of the same inventor.

NECKTIE.—Miner W. Bruce, Knox Center, Neb. This tie has two retaining tapes extending from opposite ends of the shield partly encircling the collar, one of the tapes being permanently secured to the shield and the other detachable, both tapes carrying hooks adapted to engage apertures arranged in the sides of the collar.

HOSE SUPPORTER.—Miner W. Bruce, Knox Center, Neb. This supporter consists of an elastic divided band having hooks attached to its ends, a clasp for attachment to the hose also having a hook, while an endless cord is passed around all the hooks and slides freely thereon, any slack in the elastic band of the supporter being automatically taken up by the clasp-carrying cord.

GARTER.—Jacob Katzenberg, New York City. This garter consists of an elastic tape having its ends united by a metal clasp applied to the tape a short distance from its extremities, the ends being left free to form the bow pieces which cover the clasp at the front.

SYRINGE.—Jay W. Kirkwood, Silver Mountain, Idaho. This is a medical syringe having inner and outer chambers connected with each other at or near their rear ends and both having openings through the forward end of the syringe, a piston working within the inner chamber, whereby the syringe operates simultaneously to discharge a medicated fluid and to remove by suction foreign matter.

NEW BOOKS AND PUBLICATIONS.

INCANDESCENT WIRING HAND BOOK. By F. B. Badt. Electrician Publishing Company, Chicago, Ill. 1889. Pp. 66. Price \$1.

The practical side of electric wiring, with the electrical arithmetic necessary for "house engineering" is treated of by the author in a clear and succinct style. Numerous illustrations are embodied in the text, and the manual is one that will, we doubt not, be well received by the profession generally. It is a hand book, a code to be always at hand, as well as in the library. The need for a practical discussion of electrical problems is a growing one, and all worthy accessories to the literature of the subject are to be welcomed.

ACADEMY ARCHITECTURE AND ARCHITECTURAL REVIEW. Quarto pamphlet. Pp. 102. Edited and published by Alex. Koch and C. W. English, Chancery Lane, W. C., London, England. Wm. Mueller, New York. Price \$2.50.

We are informed that the European edition met with so much success that the London publishers decided to issue an American edition. Every page contains one or more plates of buildings, bits of detail or architectural sketches from an English point of view without any descriptive text. The work is arranged in two parts, the first containing miniature reproductions of designs, studies and sketches of architectural work that were exhibited at this year's academy exhibition, and the second part, designs of notable buildings executed within the last five years, confined however to European work. The most notable work at the Academy is reproduced, particularly an interior view of Mr. E. R. Robson's People's Palace reading room. Mr. D'Oyly Carte's new theater in Cambridge Circus by T. E. Colcutt, the famous Hotel Metropole at Brighton, in Mr. Waterhouse's best style, also a chapel in Duke Street, Mayfair, by him, interesting from the massive yet graceful treatment of the spire. The most charming bit in the whole work is a water color sketch of a Norman gateway and library at Windsor Castle, by Phene Spiers, the famous teacher of drawing. The frontispiece is the chef d'œuvre of the English work, viz., the Brownlow Street front of University College, Liverpool, by Mr. Waterhouse. Sir Arthur Blomfield contributes a beautiful sketch of a reredos for new Church of St. Mary, Portsea. The chief works of interest in the second part are the several drawings of the Hofburg Theater, Vienna. A study of the various features of the design is full of interest. It marks the monumental feeling better than any other design exhibited. The point of view taken for the perspective does not do the noble front justice. The horizon line is too high. The elevations are much more satisfactory to one accustomed to interpret them. The publishers announce their intention to continue this work by an annual number. We wish them every possible success. The plates are excellent. More than that, there is not a poorly drawn sketch in the collection, and for one who desires to carefully study English work, no better opportunity could be found. The only regret we have to record is the evident lack of space for more sketches of plans, bits of detail, and reproductions of water color studies, such as the

beautiful work shown by Messrs. Blomfield and Phene Spiers. If English plans could have American elevations and groupings, or American elevations and feeling for contrasts could have English planning, modern architecture would be worthy of the closest study and highest praise.

L'ART D'EMPAILLER LES PETITS ANIMAUX. By Paul Combes. Librairie de la Science en Famille. No. 118 Rue d'Asques, Paris, France. This is a little pamphlet of 32 pages on the methods of mounting animals.

LA PHOTOGRAPHIE ET SES APPLICATIONS. I. LA FERROTYPAGE. Obtention directe des positifs à la chambre noire. By F. Drouin. Librairie de la Science en Famille. Paris, France. Pamphlet of 36 pages.

CONSEILS PRATIQUES AUX AMATEURS D'ELECTRICITE. Piles, sonneries, accumulateurs, allumoirs, appareils de secour, etc. Par Drouin et Huche. Pamphlet of 46 pages. Librairie de la Science en Famille. Paris, France.

CE QU'ON PEUT FAIRE AVEC LES OEUF. Collection complete et variée des expériences faciles et amusantes pouvant être exécutées par tout le monde avec des oeufs. Par Prof. Abel Cepak. Ch. Mendel, Paris, France. This is an illustrated paper-covered book of 175 pages on the various tricks and experiments that may be made with eggs.

Any of the above books may be purchased through this office. Send for new book catalogue just published.

Address MUNN & Co., 361 Broadway, New York.

SCIENTIFIC AMERICAN
BUILDING EDITION.

AUGUST NUMBER.—(No. 46.)

TABLE OF CONTENTS.

1. Elegant plate in colors of a cottage for twelve hundred dollars. Perspective elevation, floor plans, page of details, etc.
2. Plate in colors showing perspective elevation and floor plans for a small frame cottage to cost one thousand dollars. Page of details, etc.
3. Page engraving of the new and elegant Trinity church at Tiffin, Ohio, designed by F. K. Hewitt, architect.
4. A New England mansion. W. B. Tubby, New York, architect. Perspective elevation and floor plans.
5. Elevation in perspective and floor plans of a cottage at Jersey City Heights. Cost twelve thousand dollars.
6. A cottage recently erected at Bridgeport, Conn., at a cost of two thousand three hundred dollars. Floor plans and perspective.
7. A handsome country residence at Belle Haven Park, Greenwich, Conn. Cost eleven thousand dollars. Perspective and floor plans.
8. A house for eight thousand dollars, recently erected at Bridgeport, Conn. Perspective view and floor plans.
9. The New United States court house and post office, Charleston, S. C. Cost three hundred thousand dollars. Perspective and plans.
10. A cottage at Bedford Park, New York. Cost three thousand five hundred dollars. Plans and perspective.
11. House for three thousand six hundred dollars, recently erected on Armory Hill, Springfield, Mass. Perspective elevation and floor plans.
12. Page of designs of ornamental well curbs.
13. Brick dwellings recently erected in Jersey City, N. J., at a cost of three thousand eight hundred dollars each. Plans and perspective.
14. A corner residence on Jersey City Heights, N. J. Cost eighteen thousand dollars. Plans and perspective.
15. The great chapel, cathedral of Toledo, Spain, drawn by Antonio Hebert. Full page engraving.
16. Engraving of the Lessing theater in Berlin.
17. View of the new electrical laboratory of Purdue University at La Fayette, Indiana.
18. View of the street front of the handsome Brooklyn, N. Y., library.
19. Miscellaneous Contents: Hints to architects.—Iron bricks.—Hard woods.—Prevention of diphtheria. Overthrowing a chimney.—The manufacture of Roman bricks.—Woods for inside finish.—Jim Fisk's monument.—Experiments on mortar and concrete, with illustrations.—Clamp for pulling street piling, illustrated.—The Eiffel tower.—Sixteen stories the limit.—A singular fireplace explosion.—An ornamental stairway, illustrated.—The Hess system of ventilating and warming.—Hints about lawns.—Hot water heating, illustrated.—The "Timby" automatic sash lock, illustrated.—A solid guaranty for roofing plates.—High speed automatic engines.—Metallic shingles and roofing tiles.—Electrical appliances for houses, illustrated.

The Scientific American Architects and Builders Edition is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid MAGAZINE OF ARCHITECTURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and allied subjects.

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION of any Architectural publication in the world. Sold by all newdealers.

MUNN & CO., PUBLISHERS,
361 Broadway, New York.

Business and Personal.

The charge for insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

The man or woman who is profitably employed is generally happy. If you are not happy, it may be because you have not found your proper work. We earnestly urge all such persons to write to be B. F. Johnson & Co., 1009 Main St., Richmond, Va., and they can show you a work in which you can be happily and profitably employed.

Wanted—Second hand surveyor's transit. Box 274, El Dorado, Kas.

Model steam engine. Cir. free. Edgar Side, Phila., Pa.

For Sale—A valuable metallic roofing patent. No screws or nails necessary; unequaled for lightness and durability. Address Julius Klehe, Mauch Chunk, Pa.

For Sale or Royalty—Baling press, patent No. 406,680, described in SCIENTIFIC AMERICAN, No. 5, Vol. 61. Has great compressing power; light and easy to operate. Meets a long felt want of farmers, broom corn, cotton, and wool growers. Manufacturers on royalty can have a bargain. W. E. Walter, Silver City, Idaho.

The Lowrie toilet stand, illustrated in this paper, May 26, 1888 (no movable bowl or pitcher required), is now on sale in elegantly finished quartered oak, with movable top, by Wm. R. Farrand, Detroit, Mich.

For Sale.—Buckle—patent No. 407,919, July 30, 1889. For description see page 98.

Guild & Garrison, Brooklyn, N. Y., manufacture steam pumps, vacuum pumps, vacuum apparatus, air pumps, acid blowers, filter press pumps, etc.

For the latest improved diamond prospecting drills, address the M. C. Bullock Mfg. Co., Chicago, Ill.

Ball Engine.

Automatic cut-off. Ball Engine Co., Erie, Pa.

Presses & Dies. Ferracute Mach. Co., Bridgeton, N. J.

The Holly Manufacturing Co., of Lockport, N. Y., will send their pamphlet, describing water works machinery, and containing reports of tests, on application.

Screw machines, milling machines, and drill presses.

E. E. Garvin & Co., Light and Canal Streets, New York.

Planing and Matching Machines. All kinds Wood Working Machinery. C. B. Rogers & Co., Norwich, Conn.

Packer Ratchet Drills are drop forged from Norway iron and bar steel. Billings & Spencer Co., Hartford, Conn.

Rubber Belting, all sizes, 77½ per cent from regular list. All kinds of Rubber Goods at low prices. John W. Buckley, 156 South Street, New York.

Steam Hammers, Improved Hydraulic Jacks, and Tube Expanders. R. Dudgeon, 24 Columbia St., New York.

Hoisting Engines, Friction Clutch Pulleys, Cut-off Couplings. The D. Frisbie Co., 112 Liberty St., N. Y.

"How to Keep Boilers Clean." Send your address for free 96 p. book. Jas. C. Hotchkiss, 120 Liberty St., N. Y.

The best Coffee roasters, coolers, stoners, separators, polishers, scourers, glossing apparatus, milling and peaberry machines; also rice and macaroni machinery, are built by The Hungerford Co., Broad and Front Sts., N. Y.

Lathes for cutting irregular forms. Handle and spoke lathes. I. E. Merritt Co., Lockport, N. Y.

Pattern makers' lathe. Back knife gauge lathe for turning chair stock. Rollstone Machine Co., Fitchburg, Mass.

Split Pulleys at low prices, and of same strength and appearance as Whole Pulleys. Yocom & Son's Shafting Works, Drinker St., Philadelphia, Pa.

Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters, or no attention will be paid thereto. This is for our information, and not for publication.

References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all, either by letter or in this department, each must take his turn.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each. Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(1141) A. G. D.—The outside of a galvanized iron roof has a zinc surface which, being in contact with moist air, is slowly oxidized. The oxide shows as a light white powder which sticks to the hand as you brush it over the surface. Rains wash the oxide into the tank and the water absorbs it to a large degree. This is very noticeable wherever plumbing is done with galvanized pipe. The first water that is drawn after the pipe has been closed over night tastes strongly of zinc. Hence housekeepers are cautioned to always waste as much water as has lain in a galvanized pipe over night. The oxide of zinc is poisonous. The oxide of iron is not poisonous. For this reason we recommend the painting of zinc or galvanized roofs with oxide of iron paint or paint made from pulverized slate or mica. Even a coat of boiled linseed oil will protect the roof from oxidizing. A physician or druggist should be able to advise you as to the effect of using the water from a galvanized roof. Any person using spring water should be able to detect the zinc taste in the water from your roof.

(1142) J. S.—The rule of your council in regard to kind of pipe and fittings is very absurd. The universal practice in the United States for gas fitting is to use black iron pipe, malleable iron fittings,

tees, and elbows. Bending and offsetting of the pipe is a matter of economy or taste with the pipe fitters. Offsets are generally bent if not too large to insert conveniently. Bends made on ends of small pipes $\frac{1}{4}$ inch, $\frac{1}{2}$ inch, and $\frac{3}{4}$ inch, for terminals for chandelier and bracket connections, are properly used to prevent unscrewing of the short piece through the plastering. These bent pieces have a piece of flat iron or a strap soldered to them so as to anchor the pieces for solid support to the chandeliers and brackets. The licensing and registration of gasfitters and plumbers is a subject of municipal regulation in all large cities.

(1143) O. E. Z. asks: 1. Is not an amperere the current produced by one volt through the resistance of one ohm? If so, how can a dynamo have a capacity of 130 amperes and 100 volts? A. Yes. The capacity of a dynamo in amperes is calculated by dividing the electromotive force by the resistance. 2. What does E. M. F. indicate? A. E. M. F. stands for electromotive force. Electromotive force is the power of the current to overcome resistance. 3. Watt? A. A watt is the unit of electrical power. It is equal to a volt multiplied into an ampere; 746 watts constitute an electrical horse power.

(1144) G. B. asks (1) information on blue printing and reproduction of drawings. A. We refer you for blue printing, etc., to SCIENTIFIC AMERICAN SUPPLEMENT, No. 584. In other numbers you will find much information on this line of subjects, for which we refer you to our index of papers in SUPPLEMENT. 2. For a good recipe for waterproof, India, or drawing ink. A. For waterproof drawing ink rub up the pigment with a solution of shellac in hot borax solution. This will be nearly waterproof.

(1145) J. M. D. asks: 1. What is the best material to use for a diaphragm in non-electric or an electric telephone? A. For an acoustic telephone used a diaphragm made of wood, pasteboard, sheet iron, or strained parchment. For an electric telephone use an iron diaphragm. 2. Does the material of which a telephone box (or case) is composed have an effect on the sound? A. Probably the box acts to some extent as a resonator, but it has no great effect upon the sound. 3. If so, what is the best material for such use? A. Such wood as soundboards are made of, spruce for example.

(1146) S. J. asks for a chewing gum, having some cereal in its composition. A. Take of balsam tolu 4 ounces white resin 16 ounces, sheep's suet $1\frac{1}{2}$ ounces, more or less of the latter according to the season. Of this preparation take 2 ounces, soften in a water bath and mix in 1 ounce white sugar and 3 ounces oatmeal. Roll portions of proper size in sugar or flour and form in sticks to suit.

(1147) E. B. asks a good recipe for compressed yeast and the length of time it will keep. A. Vienna yeast is said to be thus made: Indian corn, barley, and rye (all sprouting) are powdered and mixed and macerated in water at a temperature from 149° to 167° Fah. Saccharification soon takes place, when the liquid is drawn off so as to be clear, and a very little yeast is added. The yeast forms a thick scum on the surface. It is removed, drained, and pressed in a hydraulic press. It may be removed several times. It will keep from 8 to 15 days.

(1148) E. N. B. asks: 1. Which city furnishes the greatest yearly output of steel rails, St. Louis or Pittsburg? A. Pittsburg. 2. What is the best authority in chess for amateur players? A. The new edition of chess, by G. H. Gossip, which we can mail for \$3. We also refer to numerous SCIENTIFIC AMERICAN SUPPLEMENTS. 3. The address of Herr Steinitz chess monthly. A. International Chess Magazine, New York city.

(1149) L. M. P. asks (1) why several seeds, mostly beans and corn, when they are being grub eaten, become notably hot. A. Because the corn is fermenting at the same time, and the slow combustion of fermentation develops sensible heat. 2. A recipe to restore clean and transparent glassware made dim and whitish by a rather long exposure to humidity. I have tried many acids, muriatic among them, and always without success. Scraping is very troublesome. A. Nothing better than scraping or other mechanical polishing will produce the desired effect. Some polishing powders, such as flour of emery, followed by rouge rubbed on with a chamois, might be superior to scraping.

(1150) J. H. K. asks: 1. How can cloth and duck lining be made waterproof, not affecting color or original finish? A. Paraffin melted in with a hot iron is very effectual, and while somewhat changing the appearance, is on the whole about the best application. 2. What is the smallest space in which heat can be generated, not using fire? A. For very intense heat the voltaic arc, where the temperature can be further intensified by the concentration of the sun's rays thereon by a concave mirror or convex lens. The secondary spark due to opening and breaking an electric circuit is extremely small and represents a certain degree of heat.

(1151) F. D. M. asks how to clean out the rust from an iron water pipe. My pipe is 800 feet long, three-quarter inch, and is so filled up with rust that the water barely runs through it. A. The pipe cannot be cleaned out without taking it apart and cleaning each piece with a rod. It is not profitable to lay small wrought iron pipe that is not galvanized. It soon rusts and stops up. Galvanized pipe does not rust, and if the water is kept running all the time, it will be safe and free from contamination from the zinc coating.

(1152) G. E. H. asks the best method of soldering automatic sprinklers, the solder being applied to brass or phosphor bronze, and the desire being to make a joint that will not weaken with age and that will only be affected by such a degree of heat as indicates the proximity of fire. A. A solder made 1 part each of tin and lead and 2 parts bismuth, melting at 200° Fah., is usually used for sprinklers. Use soft or white resin or Venice turpentine for flux in soldering. A blow pipe is better than a copper, as the copper is slightly absorbed by the solder, which may change its melting point.

(1153) T. S.—For a description of the new government cruiser Baltimore, see SCIENTIFIC AMERICAN, July 20, 1889. For the theory of the compound engine, see SCIENTIFIC AMERICAN SUPPLEMENT, No. 204.

(1154) R. writes: The purpose of the chip inclosed is to color small articles and especially Easter eggs. It is used by stirring the chip in a cup of hot water until the color is extracted from chip. Then the article is allowed to remain in this water for a few moments. I have seen the following colors prepared in this way: Red, purple, blue, and yellow. How is this composition prepared? A. Dissolve aniline colors of the desired tint in alcohol and mix with a hot solution of gelatine. Dip the chips into this and allow them to dry. You may, while they are still moist, dip them in the dry colors so as to cause some to adhere. You may also substitute gum arabic for gelatine.

(1155) J. H. P. asks: What paper gives full account of comets? A. See SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 284, 260, 323, 330, 331, 343, 172, 173, 313.

(1156) F. N. asks the price of tin per pound, also if there are any mines in the United States producing tin. A. It is about 20 cents per pound. It has been found in Dakota, in the Black Hills, but as yet in comparatively small quantities.

(1157) C. H. G. writes: 1. What is a madstone? Are there any well authenticated cases where hydrophobia has been prevented by applying a madstone to the wound caused by the bite of a mad dog? A. The madstone is a porous stone that acts by capillary attraction to withdraw the venom from a newly made wound. It is doubtless of some effect in such cases. A carbonized deer's horn has been recommended for the purpose.

(1158) L. L. P. asks how sulphur acts to free tin from zinc when sprinkled on the melted alloy? A. The sulphur combines with the zinc, forming sulphide of zinc, which separates from and tends to float upon the melted tin.

(1159) J. K. asks a formula for erasing the white stains that occur in some of the bricks in newly constructed buildings? A. Wash with dilute muriatic acid.

(1160) H. A. Z. asks: Can cast iron be made stronger, and suitable for a small cannon, by the addition of aluminum in ladle, and what proportion would be best? Also, could copper, aluminum, and iron be used for the above? A. One-tenth of one per cent of aluminum mixed with cast iron by placing the required quantity in the ladle before tapping largely increases its strength and solidity; 5 to 10 per cent aluminum with copper makes aluminum bronze, which is nearly as strong as steel. One-tenth of one per cent of tin in cast iron also increases its strength and solidity. Copper is of doubtful effect when mixed with cast iron.

(1161) C. F. R. asks: How many feet fall of water is necessary to obtain a pressure of 25 pounds per square inch? A. 57½ feet is the hydrostatic column of water equal to 25 pounds pressure.

(1162) Amateur writes: Is there any formula or recipe for a mixture into which cardboard, used for outdoor signs, can be immersed, and made superficially, or better still thoroughly, waterproof? A. Heat the cardboard in melted paraffin, as hot as the paper will stand.

(1163) M. R. asks: 1. What does the word feathering mean as applied to the wheels of the new steamer Puritan? A. A feathering wheel has its buckets pinioned to be movable by an arm and connected with an eccentric, so that the buckets dip and leave the water vertically. 2. Is the Redeman-Tilford steel process used in the manufacture of steel plates for steamboat boilers, and if so, where? A. We have no information as to the localities of steel works using the Redeman-Tilford process. Steel plate for boilers is known in the market as Bessemer or open hearth steel. Its individual quality is quoted under certain stamps or the makers' names. 3. Does the United States marine law confine steamboat builders to certain established forms of steam boilers, and so forbid or make impossible novelties or improvements? A. United States marine inspectors have not established special forms for boilers. The regulations relate to quality and strength of material. The inspection of boilers covers also the elements of safety in form. 4. I want to build an arch in a furnace; fire brick and fire clay mortar will not withstand the heat for any time. What material must I use? A. Fire brick and fire clay are used in our hottest furnaces. Use only No. 1 extra brick and fire mortar made with the same kind of brick pulverized mixed with best fire clay. There is great difference in the quality of fire brick on the market.

(1164) W. M. L. asks how much of a resistance coil would be required to reduce a 500 volt current (of the Thomson-Houston) to the right strength for simple electric motor. A. No general rule can be given; try it on a shunt circuit from main line. House connections often act as resistance coils. If the current is of the alternating type, the motor will not work. 2. Would an amalgamated zinc interfere with the current, if a solution of rock salt be used as a solution, with copper as the other pole? A. It will by its resistance, and according to the order of the plates will increase or decrease the electromotive force. 3. Has lightning ever been measured with regard to volts and amperes? A. Not accurately. It is of many thousand volts potential. We do not understand your fourth query.

(1165) J. M. asks (1) how to make the cakes of paint, black and colors, used in stenciling. A. See answer to query No. 1006. 2. How to make a plaster cast of a hand or foot. A. Oil the hand. Provide a soft pillow, and cover it with a towel, and over that a newspaper. The hand is pressed down into this until partly embedded, and the plaster mixed with alum water is poured over it and backed up by a stiffer portion. The hand must be kept perfectly still, of course; in a few minutes the plaster will have set. It is now removed from the hand, the faces smoothed and rubbed with lard, the hand replaced, and a second cast-

ing taken of the other side. Owing to the use of the lard, the two will easily separate and will form a complete mould for casting an image in. Oil the mould before using it. It may be made in several pieces. If a man's hand with hair upon it is the object, it should first be shaved. Instead of a pillow, sand may be used for the embedding material. Care must be taken to avoid "undercutting." The foot is an easier object, but little embedding being required for the first casting.

(1166) E. B. writes: 1. I want to dissolve or disintegrate a composition in nature like glass or porcelain which is subjected when fused to great heat—white heat at least; can it be done? A. This can be done by fusing the finely powdered material with carbonate of soda, or more simply by treatment with hydrofluoric acid in a platinum dish. 2. Is there any acid which will attack glass or porcelain? A. Hydrofluoric acid. 3. Can feldspar, after being fused as described, be dissolved? A. By the fusion method or treatment with hydrofluoric acid. 4. What acids will destroy platinum? A. It dissolves in the presence of chlorine. A mixture of 3 parts hydrochloric and 1 part nitric acids is often used for its solution.

(1167) C. E. G. asks: 1. What acid will dissolve platinum? A. See answer to preceding query. 2. What acid will separate platinum from lead? A. To neutral solution of platinum add sulphuric acid, which will precipitate the lead as sulphate, leaving the platinum in solution.

(1168) Courier.—The plant sent for identification is the common plantain, *Plantago major*, L., one of the commonest of weeds.

(1169) R. J. P. asks: At what height do the clouds generally float? A. The height varies from the level of the ground, when they constitute fog or mist, to several miles. As a mean, 1,300 to 1,500 yards in winter and 3,300 to 4,000 yards in summer are given. Gay-Lussac observed clouds over 7,650 yards above the earth.

(1170) M. O. K. asks: What process is best to extract the strength from sage leaf to get it strong and preserve it? A. Distill off the oil by boiling with water and collecting the distillate, separating by decantation the oil from the water.

(1171) J. W. asks for a good receipt for cementing rubber to earthenware or chinaware so that it will stand ordinary rinsing or washing in tepid water. A. Soak strong shellac in ten times its weight of strong ammonia for three or four weeks. This makes a liquid cement, which, however, will not stand much heat. Or try a mixture of 1 part gutta percha with 10 parts asphalt melted together.

(1172) D. L. B. asks for a good formula for aromatic toilet vinegar. A. A number of formulas are given, such as the following:

a. Cologne extract.....	2 oz.
Alcohol.....	3 pt.
Acetic acid.....	$\frac{1}{2}$ "
Orange flower water.....	$\frac{1}{2}$ "
b. Extract of cassia.....	$\frac{1}{2}$ pt.
" " violet.....	$\frac{1}{2}$ "
" " rose.....	$\frac{1}{2}$ "
Tincture of orris.....	$\frac{1}{2}$ "
White wine vinegar.....	2 "
Digest for ten days and filter.	

TO INVENTORS.

An experience of forty years, and the preparation of more than one hundred thousand applications for patents at home and abroad, enable us to understand the laws and practice on both continents, and to possess unequalled facilities for procuring patents everywhere. A synopsis of the patent laws of the United States and all foreign countries may be had on application, and persons contemplating the securing of patents, either at home or abroad, are invited to write to this office for prices, which are low, in accordance with the times and our extensive facilities for conducting the business. Address MUNN & CO., office SCIENTIFIC AMERICAN, 361 Broadway, New York.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted

July 30, 1889,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Acid, making paraoxybenzoic, B. R. Seifert.....	407,906
Alarm. See Burglar alarm.	
Alloy for secondary battery plates, E. R. Knowles.....	408,182
Alloy, non-magnetic, Osterman & Lacroix.....	408,130
Animal trap, H. Barry.....	407,887
Ant trap, E. E. Davis.....	407,889
Antimony, double sulphate of, C. J. E. De Haen.....	407,925
Anvil, farrier's, J. T. Nichols.....	407,833
Armatures, protecting case for, A. L. Riker.....	408,045
Axle lubricator, carriage, J. A. Wilson.....	408,155
Bale tie machine, wire, W. A. Laidlaw.....	408,114
Baling press, W. M. Denman.....	408,089
Baling press, W. A. Laidlaw.....	408,115
Ballot box, registering and canceling, L. M. Foster.....	408,063
Band cutter and feeder, L. Close.....	408,084
Band cutter and feeder, D. West.....	407,863
Basin, set wash, W. Scott.....	407,798
Basket, waste, J. H. Osborne.....	408,129
Batteries, gelatinizing electrolytes for galvanic, P. Schoop.....	408,138
Batteries, means for measuring and regulating the charge and discharge of secondary, W. P. Kookozey.....	408,112
Battery. See Galvanic battery. Secondary battery.	
Bed, folding, C. L. Gill.....	408,171
Bed, portable folding, W. W. St. John.....	408,144
Belt fastener, W. H. Bristol.....	408,161
Belt gear, reversing, H. E. Smith.....	408,049
Bench. See Wash bench.	
Bicycle, L. A. Hill.....	407,930
Bill or tariff holder, M. T. Freeman et al.....	407,557
Binder, temporary, A. G. Fisher.....	408,008
Bit. See Boring bit.	

Boat raising and lowering apparatus, F. A. L. De Gruyter.....	407,891, 407,892
Bobbin, D. P. Mills.....	407,831
Boiler. See Sectional boiler. Steam boiler.	
Water tube boiler.	
Boiler furnace, steam, J. L. Gill, Jr.....	408,068
Boiler house, steam, J. L. Gill, Jr.....	408,172
Boiler tubes, tool for cutting out, S. E. Condon.....	408,162
Boilers, water regulator for, R. B. Brown.....	407,991
Book, blank, R. A. W. Winzenburg.....	407,886
Boot, felt, M. N. Drake.....	407,774
Boot or shoe nail, C. W. Glidden.....	408,173
Boots or shoes, tacking tool for, T. Brining.....	408,160
Boring bit, J. C. Middleton.....	407,868
Box. See Ballot box. Card and check box. Letter box. Paper box. Signal box.	
Bracket. See Desk bracket.	
Braid roll and small spool feeder, J. H. Morrison.....	408,187
Brake. See Wagon brake.	
Brake beam, E. W. M. Hughes.....	408,021, 408,025
Brake coupling, automatic air, P. G. Roquemore.....	407,839
Bridge guard, J. Ayres.....	408,064
Bridges, safety gate for swing, N. Schlessner.....	407,967
Brushes, manufacture of, J. A. Read.....	407,900
Buckle, W. Blum.....	407,919
Buckle, C. A. Mann.....	408,035
Bulkhead, W. T. Sylvan.....	408,146
Burglar alarm, T. J. Gordon.....	408,010
Burial casket, T. McGovern.....	407,897
Burial casket, J. D. Ripson.....	407,792
Burner. See Gas burner. Gas heating burner.	
Cable grip device, J. T. Hodgins.....	408,208
Calculating device, price, S. Hoadley.....	407,835
Calelectric generator, E. G. Acheson.....	407,761 to 408,041
Calendar, L. H. Orr.....	408,041
Can cover, milk, J. C. Vail.....	407,975
Can filling machine, F. M. Nichols.....	407,943
Car coupling, D. L. Barnes.....	407,808
Car coupling, J. E. Davis, Jr.....	407,996
Car coupling, E. P. Eastwick, Jr.....	407,821
Car heater, railway, Kranwenkel & Kelley.....	408,113
Car roof attachment, W. P. Settles.....	408,139
Car wheels, making wrought iron, S. M. Vaucrain.....	408,056
Cars, bolster beam for, E. W. M. Hughes.....	408,023
Cars, card holder for, W. E. Thurber.....	408,064
Cars, center plate for railway, E. W. M. Hughes.....	408,032
Cars, combined stake and pocket for, E. W. M. Hughes.....	408,028
Cars of inclined railways, safety catch for, W. C. D. Body.....	407,947
Cars, pedestal for railway, E. W. M. Hughes.....	408,029
Cars, shot-proof cage for railway, A. W. Mitchell.....	407,832
Cars, stand box for railway, H. W. Jordan et al.....	408,178
Carbureting air, apparatus for, Deboutteville & Malandin.....	407,908
Card and check box, B. Dreyfuss.....	407,855
Carpet stretcher, S. C. Harlan.....	407,823
Carriage bow, G. V. Montgomery.....	407,959
Carriage, child's, A. Woodward.....	407,916
Carriage jack, L. S. Monk.....	407,869
Carrier. See Hay carrier.	
Case. See Shipping case.	
Cash indicator and register, T. Carney.....	407,815
Cash indicator and register, H. A. Miles.....	408,036
Casting wheels, mould for, J. W. Hill.....	408,105
Cereals, scouring and decorticating, W. Ager.....	408,063
Chair, G. E. Lord.....	408,118
Churn, B. Mitchum.....	408,126
Cigar machines, apron for, J. J. Becker.....	408,067
Clamp. See Hoof clamp.	
Clasp. See Corset clasp.	
Cleaner. See Flue cleaner. Seed cleaner.	
Clip. See Hame clip.	
Clip or saddle rake tooth holder, L. W. O'Brian.....	408,128
Clock, calendar, A. F. Wells.....	407,997
Clock for use in exposed places, electric, A. Speer.....	407,945
Closet. See Dry closet. Water closet.	
Cloth calendering roll, W. S. Granger.....	407,858
Clothes pounder, J. Woolridge.....	407,807
Clutch, friction, W. D. Gray.....	408,012
Cock for self-lighting gas fuel burners, Willing & Kiefer.....	407,884
Coffee pots, percolator for, J. M. Chadwick.....	408,081
Coffin, J. H. Dunn.....	408,169
Coke oven, A. Weber.....	407,879
Confectionery, machine for making, Knorpp & Mayer.....	407,935
Corn sheller, H. Lippold, Jr.....	407,829
Corset clasp, W. F. Brooks.....	407,770
Cot, folding, J. G. Smith.....	408,141
Coupling. See Brake coupling. Car coupling. Hose coupling. Pipe coupling. Shaft coupling.	
Coupling and uncoupling stick, F. W. Beall.....	408,158
Counting mechanisms, testing device for, P. C. Illgen.....	407,932
Cracker cutting die, C. Hermann.....	407,929
Crusher. See Harrow and clod crusher.	
Crushing and grinding mills, feeding crusher for, J. F. Winchell.....	407,885
Cultivator, R. H. Avery.....	407,766
Cultivators, shovel standard for, M. L. Kissell.....	407,780
Curbing section, metallic, H. W. White.....	408,057
Curtain drying frame, J. C. Teepe.....	407,909
Cutlery handles, making, A. Johnston.....	407,826
Cutter. See Band cutter.	
Cutting paper, trimming shades, etc., tool for, C. T. Ridgley.....	408,193
Dental engines, stop motion for, A. R. Cooke.....	407,950
Derrick, portable, M. C. Bullock.....	407,993
Desk bracket, G. P. Davis.....	408,067
Die. See Cracker cutting die.	
Digger. See Potato digger.	
Dip net frame, C. E. Wheeler.....	407,979
Distance instrument, W. Barton.....	407,767
Distance instrument, A. B. Melhouse.....	407,786
Doubling machine, J. H. Shearn.....	408,140
Dough, machine for forming loaves of, F. Westerman.....	407,978
Dry closet, A. M. Coyle.....	408,086
Dust collector, E. Bretney.....	408,074
Dust collector, J. M. Case.....	407,949
Dye, compound orcin, R. Greville-Williams (r).....	11,016
Dynamo, alternating current, G. Pfannkuche.....	407,875
Electric lighting system, F. E. Kinsman.....	407,895
Electric meter, E. R. Knowles.....	408,016, 408,017
Electric motor, alternating current, E. Thomson.....	407,844
Electric projector, J. J. Wood.....	407,914
Electric switch, H. T. Riggs.....	408,194
Electrical indicator, E. R. Knowles.....	408,018
Elevator. See Hydraulic elevator.	
Engine. See Gas engine. Gas motor engine. Locomotive engine. Rotary engine. Steam engine.	
Envelope machine, A. D. Tyrrel.....	408,200
Extension joint or splice, L. A. Tarring.....	407,795
Extractor. See Lemon juice extractor.	
Eyeglass frame, self-adjusting, F. W. Nolte.....	407,789
Eyeglasses, R. C. Kennedy.....	408,109
Eyeglasses, electric, H. Welcker.....	408,151
Fan for rocking furniture, McCormas & Fitzhugh.....	408,188
Fare box attachment, F. B. Brownell.....	408,076
Felly support, wheel, L. Harris.....	408,103

Fence machine, wire, J. Decker..... 408,164
 Fifth wheel, vehicle, J. Woods..... 407,884
 Filter for rain water, J. Dornbier..... 407,854
 Finger nail guard or protector, J. J. Stoll..... 408,062
 Flue cleaner, J. Ehrlich..... 407,856
 Fodder cutting machine, corn, P. J. Jordau..... 407,827
 Folding machine, Fowler & Henkle..... 408,085
 Frame. See Curtain drying frame. Dip net frame.
 Eyeglass frame. Truck frame.
 Fruit driers, heating drum for, N. C. & J. I. Clem-
 ent..... 408,083
 Fruit pitting machine, J. Rosasco..... 407,965
 Furnace. See Steam boiler furnace.
 Furnace for burning bone-black, A. Weber..... 407,912
 Furnace grate, M. H. Maskovits..... 407,873
 Furnace or other door, G. E. Wilbur..... 407,980
 Furnaces, apparatus for charging and drawing, S.
 T. Wellman..... 408,152
 Furniture, school, J. Peard..... 408,134
 Fuses, cap for, W. H. Frazer..... 408,096
 Gauge. See Micrometer gauge. Steam gauge.
 Galvanic battery, C. J. Hirlmann..... 407,931
 Galvanic battery, W. P. Kookogey..... 407,781
 Garter, J. Katzenberg..... 408,179
 Gas burner, incandescent, J. L. Stewart..... 408,051
 Gas, charging liquids with, C. A. Catlin..... 407,818
 Gas engine and carburetor, combined, L. F.
 McNett..... 407,961
 Gas governor, H. J. Bell..... 408,071
 Gas heating burner, H. J. Bell..... 408,073
 Gas motor engine, H. J. Purnell..... 408,137
 Gas washing apparatus, E. Ledig..... 407,936
 Gate, E. O. Aldrich..... 407,986
 Gate, W. L. Haas..... 407,961
 Gate, J. E. Little..... 408,117
 Generator. See Calelectric generator. Hot water
 generator. Steam generator.
 Glazier's diamond, J. Urbanek..... 408,055
 Glue cutting apparatus, Keller & Conly..... 407,865
 Gold surface, ornamenting, L. Jagielky..... 407,963
 Governor, steam engine, E. F. Williams..... 408,153
 Grain from elevators, apparatus for drawing off
 and mixing the, W. H. Sprague..... 407,907
 Grain hulling and reducing machine, G. A. Buch-
 holz..... 408,077
 Grain separator, W. F. Kehm..... 407,956
 Grate, fireplace, J. C. Barry..... 407,969
 Gridiron, W. C. Perkins..... 408,136
 Guard. See Bridge guard. Finger nail guard.
 Hame clip, P. Penner..... 407,834
 Hame strap fastener, E. M. Dillard..... 407,893
 Handle, E. P. Nobbs..... 407,898
 Hanger. See Pulley hanger.
 Harness, Cramberg & Ranck..... 407,882
 Harrow, A. T. Van Slyke..... 407,846
 Harrow and clod crusher, L. B. Phelps..... 407,791
 Harrow, disk, C. S. Ruef..... 408,196
 Harvester, corn or sorghum, J. J. Singley..... 407,944
 Harvester, grain binding, Cooley & Pridmore..... 408,163
 Hatchways, device for operating elevator, Bards-
 ley & Croford..... 407,849
 Hay carrier, J. A. Cross..... 407,924
 Heat from steam engines and similar apparatus,
 apparatus for utilizing waste, H. S. Robinson..... 407,838
 Heater. See Car heater. Tank heater. Water
 heater.
 Heating apparatus, regulator for hot water, E.
 Major..... 407,734
 Heating apparatus, water, J. Fries..... 408,008
 Heel attachment, C. Grumbach..... 407,860
 Hinge, W. J. Boda..... 407,809
 Hod, Schubert & Maierhofer..... 407,968
 Holder. See Bill or tariff holder. Hose holder.
 Label or card holder. Sash holder. Shade
 holder.
 Hoof clamp, A. H. Carroll..... 408,080
 Hoof expander, F. K. Dowler..... 407,820
 Hook, C. H. Thurston..... 407,797
 Hoop cutting machine, O. Schimansky..... 407,841
 Hopples, cast-off device for, H. D. McKinney..... 408,040
 Hose coupling, brake, E. A. Leland..... 408,116
 Hose holder, W. C. Willis..... 408,068
 Hose supporter, M. W. Bruce..... 407,810
 Hot water generator, P. G. Van Wile..... 407,878
 House. See Boiler house.
 Hydrant, self-closing, C. G. Ette..... 408,091
 Hydraulic elevator, W. F. Toothaker..... 408,149
 Indicator. See Cash indicator. Electrical indi-
 cator.
 Ink grinding slab, W. X. Stevens..... 408,143
 Insulating composition, F. Marquard..... 407,896
 Integrating apparatus, H. Hollerith..... 408,106
 Iron. See Sash iron.
 Iron in blast and puddling furnaces, compound
 for purifying, N. Booth, Sr..... 407,921
 Ironing table, folding, J. D. Pace..... 407,790
 Jack. See Carriage jack. Lifting jack.
 Jail. Revolving, E. Rowe..... 407,877
 Joint. See Extension joint.
 Kaleidoscope, J. W. Lovibond..... 407,937
 Kiln for burning bone black, A. Weber..... 407,976
 Kitchen, cabinet, G. E. Miller..... 408,125
 Knife. See Pocket knife.
 Knitting machine, E. Murby..... 407,980
 Knitting machine, circular, C. E. Bean..... 407,917
 Knitting machine, circular, C. Frederick..... 408,170
 Knitting machine, circular, Frederick & Egley..... 408,007
 Knitting machine, circular, E. E. Kilbourn..... 408,110, 408,111, 408,180, 408,181
 Knob attachment, J. Schade..... 407,902
 Knobs, making parts of hollow door, C. O. Case..... 407,817
 Label or card holder, J. J. Gould..... 408,009
 Lamp, H. E. Shaffer..... 407,969
 Lamp, central draught, E. H. Peck..... 408,135
 Lamp, focusing arc, J. J. Wood..... 407,915
 Lamp, incandescent gas, H. J. Bell..... 408,068, 408,069, 408,072
 Lamp, regenerative, J. F. E. W. Schmidt..... 408,197
 Lamp support, electric, A. T. Thompson..... 407,973
 Lamps, suspension device for, W. C. Homan..... 408,107
 Lathes, tool holder and rest for, L. S. Springer..... 407,972
 Laundry press, A. Otte..... 408,132
 Lemon juice extractor, J. P. Manny..... 408,121
 Lens blocking, J. J. Bausch..... 407,980
 Letter box, Moore & Chappell..... 407,870
 Lifting jack, L. Miller..... 407,788
 Lighting device, W. H. & H. P. Wilder..... 407,883
 Lock. See Sash lock.
 Lock, T. Taylor..... 408,147
 Lock and latch combined, Folsom & Davis..... 407,926
 Locomotive engine, M. N. Forney..... 408,004
 Log boom, W. H. Roan..... 408,046
 Loom, narrow warp, G. C. Moore..... 407,872
 Loom shuttle, P. T. Litchfield..... 407,968
 Loom shuttle, G. C. Moore..... 407,871
 Lubricator. See Axle lubricator. Sight feed
 lubricator.
 Mail bag fastener, L. Crepe..... 407,853
 Mail bag fastening, B. M. Moore..... 408,039
 Mailing machine, E. Woodward..... 408,202
 Mandrel, blacksmith's, J. W. Cheney..... 407,851
 Mantles, production of incandescent, F. L. & W.
 S. Rawson..... 407,983
 Mat. See Wire mat.

Measuring instrument, electric, J. A. Barrett..... 408,157
 Meter. See Electric meter.
 Micrometer gauge, F. Schlatter..... 407,903
 Middles purifiers, dust collector for, J. M. Case..... 407,948
 Mill for treating fiber yielding materials, J. D.
 Stanley..... 408,142
 Mouldings, machine for coating and embossing,
 H. Zitzewitz..... 407,847
 Motor. See Electric motor. Spring motor. Water
 motor.
 Motor, E. B. Newcomb..... 407,942
 Mower, A. B. Graham..... 408,100
 Mowing machine, G. R. Parker..... 408,133
 Mowing machine, J. F. Steward..... 408,050
 Mustache protector, J. O. Hibbard..... 408,013
 Nail. See Boot or shoe nail. Shoe nail.
 Necktie, M. W. Bruce..... 407,811
 Nut, top prop, A. Searls..... 407,904
 Organ, mechanical, E. S. Votey..... 407,801
 Organ, reed, E. S. Votey..... 407,800
 Organs, driving and governing mechanism for, E.
 S. Votey..... 407,802
 Package, utility, A. R. Waller..... 407,910
 Packing and sales case, Berlin & Wright..... 407,918
 Pall, shipping, H. Howe..... 408,108
 Paper bag machine, H. C. Burdick..... 407,813
 Paper bag machinery, C. B. Stillwell..... 407,794
 Paper bags, manufacture of, H. C. Burdick..... 407,814
 Paper box, H. Roensch..... 407,964
 Paper cutting machines, cutting stick for, J. E.
 Hamilton..... 407,861
 Paper making machines, dandy roll for, R. Brown..... 407,932
 Paper or other sheets from a pile, mechanism for
 feeding, E. Woodward..... 407,985
 Paper pulp screen, C. H. Campbell..... 407,995
 Pawl and ratchet mechanism, H. H. Dille..... 408,080
 Pen, fountain, D. C. Demarest..... 407,999, 408,000
 Pigeonhole, W. H. Taylor..... 408,053
 Pigeonholes, metallic bottom plate for, I. L.
 Dunn..... 408,001
 Pillow, folding, A. W. Harrison..... 407,776
 Pipe, bending and coiling, H. E. Fowler..... 408,005
 Pipe coupling, W. M. Brown, Jr..... 407,922
 Pipe, machine for bending and coiling, H. E.
 Fowler..... 408,006
 Planter, corn, R. H. Avery..... 407,848
 Planter, potato, C. W. Freyer..... 408,097
 Planting, seed, S. E. Gross..... 407,822
 Plugs, extension box and key for street gas or
 water, Kallaher & Mulrooney..... 407,955
 Plumbers' hooks, machine for making, H. Lilley..... 408,184
 Plumbers' use, saw for, R. & C. McAlpine..... 407,941
 Pocket knife, H. C. Hunt..... 407,863
 Potato digger, D. Y. Hallock..... 407,928
 Press. See Baling press. Laundry press.
 Pressure regulator, water, H. B. Williams..... 407,981
 Printing machine, Fowler & Henkle..... 408,094
 Printing presses, automatic feeder for, J.
 Schaefer..... 407,840
 Printing presses, feed gauge for, E. L. Megill..... 408,122
 Projectile, lubricating, S. A. Day..... 407,890
 Protector. See Mustache protector.
 Pulley, Lawson & Field..... 407,866
 Pulley hanger, Hyde & Horner..... 407,954
 Pulleys, yielding connection for, W. E. Davis..... 407,997
 Pulp, machine for forming bodies from successive
 layers of, Fairbanks & Parker..... 408,082
 Pump, hand force, P. Kohz..... 408,133
 Punch, check, E. L. Liedke..... 407,867
 Radiator, hot water, E. S. Manny..... 407,785
 Railway, aerial cable, Perry & McKenzie..... 407,034
 Railway rail, reversible, R. B. Burns..... 408,078
 Railway track layer, D. S. Moore..... 408,186
 Railways, automatic signal for cable, A. Pfedner..... 408,043
 Refrigerator, car, J. F. Hanrahan..... 407,862
 Refuse ejector, J. S. Wallace..... 408,201
 Regulator. See Pressure regulator. Water regu-
 lator.
 Roller mills, feed regulator for, J. W. Wilson..... 408,156
 Roofing, ceiling, or siding, sheet metal, Curtis &
 Huntley..... 407,772
 Roofing, machine for the manufacture of, G. W.
 McGraw (r)..... 11,017
 Roofing or sheathing, J. W. Beaumont..... 408,066
 Roofing sheet, metallic, L. L. Sagendorph..... 407,966
 Rotary engine, W. M. Griscom..... 408,101
 Sad iron, J. H. Dubrow..... 408,168
 Safe lock, J. C. Harris..... 407,775
 Sash holder, S. E. Harrington..... 407,962
 Scales, stop motion register for grain, F. H. Rich-
 ards..... 408,192
 Screen. See Paper pulp screen.
 Screws, machine for rolling threads on, J. Shel-
 don..... 408,048
 Sealing disk for jars, etc., D. W. Johnson..... 408,177
 Secondary battery, V. H. Ernst..... 408,002
 Sectional boiler, J. Bond..... 407,930
 Seed cleaner, cotton, R. H. Collyer..... 408,085
 Self-oiling wheel, N. D. Helmick..... 407,777
 Selling machine, automatic, J. W. Vaughn..... 407,946
 Separator. See Grain separator.
 Sewing machine, A. M. Leslie..... 408,019
 Sewing machine, overseaming, J. C. Goodwin..... 408,009
 Sewing machine, shoe welt, J. S. Turner..... 407,974
 Sewing machine treadle, W. F. Otis..... 408,131
 Sewing machine tucking guide, H. L. Nick..... 408,190
 Shade holder, H. J. Bell..... 408,070
 Shaft bearings, lubricator for, J. Comer..... 408,771
 Shaft coupling, W. D. Gray..... 408,011
 Shafts, machine for straightening, rounding, and
 condensing, G. F. Simonds..... 407,843
 Sheller. See Corn sheller.
 Shipping case, W. P. Kookogey..... 407,967
 Shirt, J. Adair..... 407,764, 407,765
 Shoe nail, wire, A. Briggs..... 408,159
 Shoestrapping fastener, J. Driscoll..... 408,167
 Shutter fastener, T. Thorn..... 407,845
 Sight feed lubricator, W. Woodward..... 407,805
 Sign, street lamp, J. Stewart..... 408,199
 Signal box, electric, D. A. Palmer..... 408,042
 Siphon, M. Siersdorfer..... 407,971
 Sled, A. Tode..... 407,798
 Sleighs, arm rail for, A. Searls..... 407,905
 Smoke box front door, E. W. M. Hughes..... 408,026
 Soldering caps on fruit cans, machine for, De Cew
 & Carpenter..... 407,773
 Soldering metal pipes, W. A. Henderson..... 407,778
 Spindle driving bands, tension regulating device
 for, A. McDonald..... 408,189
 Spinning mule, J. Lowe..... 407,783
 Spinning spindle support, G. O. Draper..... 408,165
 Spinning spindle support, W. F. Draper..... 408,166
 Spinning spindle support, T. H. Logan..... 408,165
 Spreader, N. R. Deppe..... 408,088
 Spring. See Vehicle spring.
 Spring motor, W. J. Gordon et al..... 408,175
 Spring motor, Melchior & Haas..... 407,939
 Springs, machine for making side bar, M. D. L.
 Williams..... 407,913
 Stand. See Switch stand.
 Steam boiler, J. A. Caldwell..... 407,888
 Steam engine, S. S. Williams..... 408,154
 Steam gauge, C. Winther..... 407,983

Steam generator, T. F. Morrin..... 407,940
 Steam trap, G. J. Graebert..... 408,176
 Stove, gas, L. Ketchum..... 407,933
 Stove grate, W. C. Metzner..... 407,787
 Stove ovens, door for, J. Orr..... 408,191
 Stove pipe fastener, J. Lindenmayer..... 408,020
 Stove range, oil, W. H. Wilder..... 407,882
 Stove, vapor, J. S. Butler..... 408,079
 Supporter. See Hose supporter.
 Switch. See Electric switch.
 Switch stand, N. O. Goldsmith..... 408,174
 Syringe, J. W. Kirkwood..... 407,934
 Table. See Ironing table.
 Table, S. & M. Henry..... 407,824
 Table, L. Stockman..... 407,908
 Table leaf support, T. G. Bugbee..... 407,812
 Tank heater, G. Armstrong..... 407,988
 Telephone, Trowbridge & Sheldon..... 407,799
 Tire tightener, A. Knox..... 407,828
 Tire truing machine, T. J. Reid..... 408,044
 Toe weight, J. A. Baughman..... 407,768
 Tongue, vehicle, J. P. Johnson..... 407,864
 Tool driver, A. Schuermann..... 407,842
 Toy, G. E. Troop..... 408,148
 Toy gun, T. Adams..... 408,062
 Toy race track, W. N. McManus..... 407,874
 Trap. See Animal trap. Ant trap. Steam trap.
 Tray, Z. T. Hall..... 408,102
 Treadle, J. H. Whitney..... 407,804
 Truck, E. W. M. Hughes..... 408,034
 Truck end plate, E. W. M. Hughes..... 408,030
 Truck for railway carriages, E. W. M. Hughes..... 408,022
 Truck for rolling vehicles, E. W. M. Hughes..... 408,033
 Truck frame, E. W. M. Hughes..... 408,024
 Truck, pressed steel, E. W. M. Hughes..... 408,081, 408,119
 Tubes, attaching plates to, S. R. Wilmot..... 407,982
 Tubes, making flattened, S. R. Wilmot..... 408,059
 Tug loop, harness, S. D. Harris..... 408,104
 Tug, force, J. Malquist..... 408,120
 Type, A. D. Rood..... 408,195
 Type plates, manufacture of, C. H. Perry..... 407,962
 Typewriting machine, G. W. M. Yost..... 408,061
 Type writing machines, cam motion for, F. L.
 Twiss..... 408,150
 Umbrella tree, J. Haight..... 407,927
 Valve, flushing, G. Michaud..... 408,124
 Valve gear for engines, Woolf & Peebles..... 407,606
 Valve, safety check, M. Warren..... 407,911
 Valve, steam engine, M. C. Bullock..... 407,994
 Valve, steam engine, T. H. Haberkorn..... 407,894
 Valve, throttle, W. W. St. John..... 408,145
 Vaporizer and burner, hydrocarbon oil, J. S.
 Semon..... 408,198
 Vaporizing oil and water and superheating and
 burning the same, apparatus for, Rogers &
 Wharry..... 407,901
 Vehicle spring, N. B. Phelps..... 407,899
 Vehicle wheel, R. Bean..... 407,769
 Vehicle wheel, W. C. Hodnett..... 407,779
 Velocipede, T. B. Jeffery..... 48,014
 Velocipede, ice, J. E. Robinson..... 407,876
 Ventilator, O. B. Grant..... 407,859
 Wagon brake, S. Kauffman..... 408,015
 Walls, covering for interior, T. W. Burger..... 407,923
 Wash bench, folding, J. B. Mersman..... 408,123
 Washing machine, T. H. Carson..... 407,816
 Washing machine, J. Chambers..... 408,082
 Washing machine, W. White..... 407,881
 Watchmakers' tweezers, J. A. Miller..... 408,037
 Water closet, G. D. Moffat..... 408,038
 Water heater, N. A. Boynton..... 407,850
 Water heating and purifying apparatus, A. P.
 Creque..... 407,819
 Water motor, H. Brown..... 408,075
 Water regulator and accumulator for house pur-
 poses, A. J. L. Loretz..... 407,830
 Water tube boiler, J. Wood, Jr..... 408,060
 Welt and upper guide, combined, G. Amborn, Jr..... 407,987
 Wheel. See Fifth wheel. Self-oiling wheel. Ve-
 hicle wheel.
 Whiffletree, G. Reiter..... 407,836
 Whiffletrees and draught bars, manufacture of,
 G. Reiter..... 407,837
 Wick raiser, H. E. Shaffer..... 407,970
 Wire fastener, Barrett & Nussbeck..... 408,065
 Wire mat, S. Rogers..... 408,047
 Wire splicing tool, W. S. Lennon..... 407,782

DESIGNS.

Badge, H. M. Betz..... 19,233
 Carpet, E. G. Sauer..... 19,246
 Corsets, ornamentation of, C. A. Griswold..... 19,234 to 19,240
 Decorative fabric, C. H. Koster..... 19,243
 Drawer, O. Martin..... 19,244
 Electric wire bracket, R. Herman..... 19,241, 19,242
 Sash cord guide face plate, S. Palmer..... 19,245

TRADE MARKS.

Beer, ale, mineral waters, and carbonated (aerated) drinks, Koster & Bial..... 16,884
 Bells, H. McShane & Co..... 16,889, 16,890
 Boots and shoes of all kinds, J. E. Lentz..... 16,885
 Braids, Butler, Richards & Co..... 16,875
 Coffee, J. H. Thompson & Company..... 16,894
 Coffee extract, D. D. Williamson..... 16,873
 Deodorizer, a disinfectant and germicide com-
 pound constituting a, W. Banermann..... 16,887
 Flies, device for containing a poison solution for
 killing, Moore & Kibler..... 16,888
 Flour, wheat, C. F. Horning..... 16,882
 Hair restorer, M. A. Dodge..... 16,880
 Hose, mill, or fire, Boston Woven Hose Company..... 16,868
 Hose, rubber or cotton, Revere Rubber Company..... 16,892, 16,893
 Insect exterminators, L. Dirksen..... 16,879
 Oils, lubricating and illuminating, J. Ellis & Co..... 16,881
 Organs, reed, Mason & Risch..... 16,872
 Paper and envelopes, Z. & W. M. Crane..... 16,869, 16,870
 Rat and roach exterminator, C. D. Maurer..... 16,887
 Ropes, yarns, twines, and cords, Plymouth Cord-
 age Company..... 16,891
 Salves, G. J. Kannmacher..... 16,871
 Silver polish, Jones & Dudley..... 16,883
 Soap powder, C. Lipps..... 16,886
 Tea, Davidson & Co..... 16,877, 16,878
 Vehicle wheels, J. Bolick..... 16,876
 Watch movements, American Waltham Watch
 Company..... 16,874

A printed copy of the specification and drawing of
 any patent in the foregoing list will be furnished from
 this office for 25 cents. In ordering please state the
 name and number of the patent desired, and remit to
 Munn & Co., 361 Broadway, New York.

Canadian Patents may now be obtained by the
 inventors for any of the inventions named in the fore-
 going list, provided they are simple, at a cost of \$40
 each. If complicated the cost will be a little more. For
 full instructions address Munn & Co., 361 Broadway,
 New York. Other foreign patents may also be obtained.

Advertisements.

Inside Page, each insertion - - - 75 cents a line.
 Back Page, each insertion - - - \$1.00 a line.
 The above are charges per agate line—about eight
 words per line. This notice shows the width of the line,
 and is set in agate type. Engravings may be had at ad-
 vertisements at the same rate per agate line, by measure-
 ment, as the letter press. Advertisements must be
 received at publication office as early as Thursday morn-
 ing to appear in next issue.

USE ADAMANT WALL PLASTER

It is Hard, Dense, and
 Adhesive. Does not crack
 or peel. It is impervious
 to wind, water, and disease
 germs. It dries in a few
 hours. It can be applied in
 any kind of weather. It is
 in general use. Licenses
 granted for the mixing,
 using, and selling. Address
ADAMANT MFG. CO.
 71 E. Genesee Street,
 Syracuse, N. Y.

Patent Foot Power Machinery

Complete Outfits.
 Wood or Metal workers without steam
 power, can successfully compete with
 the large shops, by using our New
LABOR SAVING Machinery,
 latest and most improved for practical
 shop use, also for Industrial Schools,
 Home Training, etc. Catalogue free.
Seneca Falls Mfg. Co.
 635 Water Street, Seneca Falls, N. Y.

ELECTRO MOTOR, SIMPLE. HOW TO
 make. By G. M. Hopkins.—Description of a small electro
 motor devised and constructed with a view to assisting
 amateurs to make a motor which might be driven with
 advantage by a current derived from a battery, and
 which would have sufficient power to operate a foot
 lathe or any machine requiring not over one man power.
 With 11 figures. Contained in **SCIENTIFIC AMERICAN**
 SUPPLEMENT, No. 641. Price 10 cents. To be had at
 this office and from all newsdealers.

SEBASTIAN, MAY & CO'S

Improved Screw Cutting
Foot & LATHES \$60
 Power
 Drill Presses, Chucks, Drills,
 Dogs, and machinists' and am-
 ateurs' outfits. Lathes on trial.
 Catalogues mailed on application.
 165 W. 2d St., Cincinnati, O.

EDISON LAMPS

For Decorative, Experimental, and
 Surgical, Dental, and am-
 ateurs' purposes. From 1/2
 er. From 2 1/2
 Catalogue on application.
EDISON LAMP CO.
 Harrison, N. J.

TELEMETERS

Electric Indicating and Recording
THERMOMETERS, PRESSURE GAGES, BAROMETERS, HEIGHT OF WATER GAGES, Transmitters.
 See article, p. 63, *Sci. Amer.*,
 August 3, 1889.
 Receiver. Send for manufacturers' catalogue to
Standard Thermometer Co., Peabody, Mass., U.S.

C & C ELECTRIC MOTORS
 FROM 1/2 HORSE POWER UP, FOR
 DRIVING LATHES, VENTILATING
 FANS, SEWING MACHINES, PUMPS,
 ELEVATORS, GRINDING PRESSES, ETC.
 THESE MOTORS
 RUN BY ELECTRIC CURRENT
 FROM ARC OR INCANDESCENT
 LIGHT CIRCUITS OR STORAGE
 BATTERIES.
THE C & C ELECTRIC MOTOR CO.
 402-404 GREENWICH ST. NEW YORK

ICE-HOUSE AND REFRIGERATOR.

Directions and Dimensions for construction, with one
 illustration of cold house for preserving fruit from
 season to season. The air is kept dry and pure through-
 out the year at a temperature of from 34° to 36°. Con-
 tained in **SCIENTIFIC AMERICAN SUPPLEMENT No. 116**.
 Price 10 cents. To be had at this office and of all news-
 dealers.

FINE TOOL MAKERS

Send to American Watch Tool Co., Wal-
 tham, Mass., for circular of No. 3 Bench Lathe.
 A Screw Cutting Lathe 32 in. by 7 in. swing.

ASBESTOS
 MINERS & MANUFACTURERS.
 The ASBESTOS PACKING CO.
 169 CONGRESS ST. BOSTON

PETROLEUM BOAT. DESCRIPTION
 of a petroleum motor devised by Mr. Lenoir for the
 propulsion of small boats. With 2 figures. Contained
 in **SCIENTIFIC AMERICAN SUPPLEMENT No. 637**.
 Price 10 cents. To be had at this office and from all
 newsdealers.

Stored Energy

ACCUMULATORS for Electric Lighting and
 Street Car Propulsion.
ELECTRICAL ACCUMULATOR COMPANY
 No. 44 Broadway, New York City.

Edco System.

Complete Electric Light and Power Plants. Street Cars
 equipped for Electric Propulsion. The latest and most
 experienced Electric Motor Co. in the world.
THE ELECTRO DYNAMIC COMPANY.
 No. 224 Carter St., Philadelphia, Pa.

A Great Repository of Practical and Scientific Information.

One of the *Fuller, Freshest, and Most Valuable Handbooks* of the Age. Indispensable to Every Practical Man.

NOW READY.

Price \$2.00.

Free of Postage to any Address in the World.

The Techno-Chemical Receipt Book:

Containing Several Thousand Receipts, covering the Latest, most important, and most Useful Discoveries in Chemical Technology, and their Practical Application in the Arts and the Industries. Edited chiefly from the German of Drs. Winckler, Eisner, Heinze, Mierzinski, Jacobsen, Koller, and Heinzerling, with additions by William T. Brant, Graduate of the Royal Agricultural College of Elders, Prussia, and William H. Wahl, Ph.D. (Heid.), Secretary of the Franklin Institute, Philadelphia, author of "Galvanoplastic Manipulations." Illustrated by 78 engravings, one volume, over 500 pages, 12mo, elegantly bound in scarlet cloth, gilt, closely printed, containing an immense amount and a great variety of matter.

Price \$2.00, free of postage to any address in the world. A circular of 32 pages, showing the full Table of Contents of this important Book, sent by mail free of postage to any one in any part of the World who will furnish his address.

HENRY CAREY BAIRD & CO.,
INDUSTRIAL PUBLISHERS, BOOKSELLERS & IMPORTERS
810 Walnut St., Philadelphia, Pa., U. S. A.

ARCHITECTURAL BOOKS.

Useful, Beautiful, and Cheap.

To any person about to erect a dwelling house or stable, either in the country or city, or any builder wishing to examine the latest and best plans for a church, school house, club house, or any other public building of high or low cost, should procure a complete set of the ARCHITECTS' AND BUILDERS' EDITION of the SCIENTIFIC AMERICAN.

The information these volumes contain renders the work almost indispensable to the architect and builder, and to persons about to build for themselves they will find the work suggestive and most useful. They contain colored plates of the elevation, plan, and detail drawings of almost every class of building, with specifications and approximate cost.

Seven bound volumes are now ready and may be obtained, by mail, direct from the publishers or from any newsdealer. Price, \$2.00 a volume. Stitched in paper covers. Subscription price, per annum, \$2.50. Address and remit to

MUNN & CO., Publishers,
361 Broadway, New York.



BEST DRIERS for Grain, Sand, Salt, Wet Feed, Chemicals, etc. S. E. Worrell, Hannibal, Mo.

NEW YORK BELTING AND PACKING CO.

JOHN H. CHEEVER, Treas.

15 PARK ROW, New York.

OLDEST and LARGEST Manufacturers in the United States of

VULCANIZED RUBBER FABRICS

For Mechanical Purposes.

RUBBER BELTING,

Packing, Hose,

Vulcanite Emery Wheels, Rubber Mats, Matting & Treads

SALESROOMS:—Philadelphia, 308 Chestnut St.; Boston, 52 Summer St.; Chicago, 151 Lake St.; Minneapolis, 28 South 2d St.; Cincinnati, 161-165 W. Pearl St.; Cleveland, 176 Superior St.; San Francisco, 14 & 16 Main St.; Detroit, 16-24 Woodward Avenue. European Branch, Pickhuben 5 Hamburg (Freihafengebiet), Germany.

TO CONTRACTORS
WE MAKE THE LARGEST LINE OF
ROAD GRADERS, SCRAPERS, PLOWS, & RECONSTRUCTION TOOLS
FOR THE WORLD
WELLS TOOLS
WE MANUFACTURE THE LARGEST LINE OF WELLBORING TOOLS
THE WORLD
NEW ERA
Railroad Builder, Wagon Road Grader, Wagon Loader, and Ditching Machine. It will place in an embankment 1000 cubic yards of earth in 10 hours at a cost of 1 1/2 to 2 1/2 cts. per yd.
CARPENTER ST., CARROLL AVE.—CHICAGO, ILL. U.S.A.

WATCH CLEANING AND REPAIRING.—A valuable and practical paper, full of useful suggestions. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 664. Price 10 cents. To be had at this office and from all newsdealers.

OIL WELL SUPPLY CO. Ltd.

91 & 92 WATER STREET, Pittsburgh, Pa., Manufacturers of everything needed for **ARTESIAN WELLS** for either Gas, Oil, Water, or Mineral Tests, Boilers, Engines, Pipe, Cordage, Drilling Tools, etc. Illustrated catalogue, price lists and discount sheets on request.

ICE-HOUSE AND COLD ROOM.—BY R. G. Hatfield. With directions for construction. Four engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 664. Price 10 cents. To be had at this office and from all newsdealers.

ARTESIAN
Wells, Oil and Gas Wells, drilled by contract to any depth, from 50 to 300 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 600 ft. Send 6 cents for illustrated catalogue. Pierce Artesian and Oil Well Supply Co., 80 Beaver Street, New York.

Barnes' Patent Foot Power Machinery.

WORKERS OF WOOD OR METAL, without steam power, by using outfit of these Machines, can bid lower, and save more money from their jobs, than by any other means for doing their work. Also for Industrial Schools or Home Training. With them boys can acquire practical journeymen's trades before they "go for themselves." Price-List Catalogue Free. **W. F. & JOHN BARNES CO.,** No. 1999...Ruby St., Rockford, Ill.

DEEP KEEL AND CENTER BOARD Yachts.—A paper by Mr. B. Martell, chief surveyor of Lloyd's Register of British and foreign shipping, discussing the comparative merits of those two forms of craft for racing purposes. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 662. Price 10 cents. To be had at this office and from all newsdealers.

2 to 40 H.P. The MOTOR of the 19th CENTURY.
Can be used Any Place, to do Any Work, and by Any One. No Boiler! No Fire! No Steam! No Ashes! No Gauges! No Engineer! A perfectly safe Motor for all places and purposes. Cost of operation about one cent an hour to each indicated horse power. For circulars, etc., address **Charter Gas Engine Co.,** P. O. Box 148, Sterling, Ill.

SUMMER COOKING
For Home, Cottage, Camp, or Yacht reduced to simplicity by use of The Arnold Automatic Steam Cooker. A novel invention of great merit, in which anybody can cook a whole meal over one flame without attention or danger of spoiling. Prices, \$1.50 to \$6. Coffee Cookers, Urns, and Milk Sterilizers on same principle. **Wilmot Castle & Co.,** Rochester, N. Y.

RENSSELAER POLYTECHNIC INSTITUTE, Troy, N. Y. The oldest School of Engineering in the United States. Next term begins Sept. 18. The Register for 1889 contains list of graduates for 64 years, with their positions; also course of study, requirements for admission, expenses, etc. Candidates living at a distance may be examined at their homes. Address **DAVID M. GREENE, Director.**

A NEW CATALOGUE OF VALUABLE PAPERS
Contained in SCIENTIFIC AMERICAN SUPPLEMENT, sent free of charge to any address. **MUNN & CO., 361 Broadway, New York.**

Proposals for Steel Wire.—Ordnance Office, War Department, Washington, August 1, 1889. Sealed proposals, in duplicate, will be received at this office until 8 o'clock P.M., on Friday, September 20, 1889, when they will be publicly opened, for supplying the Ordnance Department, U. S. Army, with 8,000 pounds of tinned steel wire of rectangular or square cross-section, and 21,000 pounds of steel wire of square cross-section, for wrapping guns. All information required by bidders can be had upon application to **CAPTAIN C. S. SMITH, Acting Chief of Ordnance.**

Proposals for Machine Tools.—WATERVLIET ARSENAL, West Troy, N. Y., August 5, 1889. Sealed proposals, in triplicate, will be received at this Arsenal until 2:30 o'clock P.M., on Thursday, September 5, 1889, for Machine Tools required for the equipment of an Army Gun Factory. The Government reserves the right to reject all or any proposals or parts thereof. Specifications and all other information can be had on application to **COLONEL J. M. WHITEMORE, Ordnance Department, U. S. A., Commanding.**

TO INVENTORS AND MANUFACTURERS

The 58th Annual Exhibition

OF THE American Institute of the City of New York

Will Open **OCTOBER 2, 1889.** Intending Exhibitors must make early application to secure proper space and classification. For blanks and information, address **General Superintendent, American Institute, New York City.**

WATER MOTORS.
The most efficient and economical means of obtaining from one-eighth to fifteen horse power and upward. A motor which does the greatest amount of work with the use of the smallest stream of water, specially adapted for running cheaply and efficiently. Printing Presses, Elevators, Church Organs, Coffee Mills, Sewing Machines, Lathes, Dental Contrivances, and in fact, any piece of mechanism. **Binghamton Hydraulic Power Co.,** 152 State Street, Binghamton, N. Y.

VOLNEY W. MASON & CO., FRICTION PULLEYS CLUTCHES AND ELEVATORS PROVIDENCE, R. I.

DIE CUTTERS WANTED.—Permanent situation for steady and reliable men. On general work and two on spoon and fork dies. Apply in person to **TOWLE MFG. COMPANY, Newburyport, Mass.**

TOOL AGENTS WANTED
in every SHOP in the United States. Send for Catalogue Stationery &c. THE FINEST OF MECHANICAL TOOLS A SPECIALTY. **C. B. JAMES, 98 LAKE ST. CHICAGO.**

Scientific Book Catalogue

RECENTLY PUBLISHED. Our new catalogue containing over 100 pages, including works on more than fifty different subjects. Will be mailed free to any address on application. **MUNN & CO., Publishers Scientific American, 361 Broadway, New York.**

WORKING MODELS & LIGHT MACHINERY. INVENTIONS DEVELOPED. Send for Model Circular. Jones Bros. E. Co., Cin. O.

FOREIGN PATENTS
THEIR COST REDUCED.

The expenses attending the procuring of patents in most foreign countries having been considerably reduced the obstacle of cost is no longer in the way of a large proportion of our inventors patenting their inventions abroad.

CANADA.—The cost of a patent in Canada is even less than the cost of a United States patent, and the former includes the Provinces of Ontario, Quebec, New Brunswick, Nova Scotia, British Columbia, and Manitoba.

The number of our patentees who avail themselves of the cheap and easy method now offered for obtaining patents in Canada is very large, and is steadily increasing.

ENGLAND.—The new English law, which went into force on Jan. 1st, 1885, enables parties to secure patents in Great Britain on very moderate terms. A British patent includes England, Scotland, Wales, Ireland and the Channel Islands. Great Britain is the acknowledged financial and commercial center of the world, and her goods are sent to every quarter of the globe. A good invention is likely to realize as much for the patentee in England as his United States patent produces for him at home, and the small cost now renders it possible for almost every patentee in this country to secure a patent in Great Britain, where his rights are as well protected as in the United States.

OTHER COUNTRIES.—Patents are also obtained on very reasonable terms in France, Belgium, Germany, Austria, Russia, Italy, Spain (the latter includes Cuba and all the other Spanish Colonies), Brazil, British India, Australia, and the other British Colonies.

An experience of FORTY years has enabled the publishers of THE SCIENTIFIC AMERICAN to establish competent and trustworthy agencies in all the principal foreign countries, and it has always been their aim to have the business of their clients promptly and properly done and their interests faithfully guarded.

A pamphlet containing a synopsis of the patent laws of all countries, including the cost for each, and other information useful to persons contemplating the procuring of patents abroad, may be had on application to this office.

MUNN & CO., Editors and Proprietors of THE SCIENTIFIC AMERICAN, cordially invite all persons desiring any information relative to patents, or the registry of trade-marks, in this country or abroad, to call at their offices, 361 Broadway. Examination of inventions, consultation, and advice free. Inquiries by mail promptly answered.

Address. **MUNN & CO.,** Publishers and Patent Solicitors, 361 Broadway, New York.

BRANCH OFFICES: No. 622 and 624 F Street, Pacific Building, near 7th Street, Washington, D. C.

CURE for the DEAF by Fick's Pat. Improved Eustachian Tube. Whispers heard distinctly. Comfortable, invisible. Illustrated book & proof, FREE. Address or call on F. H. BLOOM, 553 Broadway, N. Y. Name this paper.

THE BOOKWALTER STEEL AND IRON CO.

Is now prepared to grant licenses under the Bookwalter, Robert, and other patents owned by it. Parties desiring licenses to operate under these patents will please state, in their application, for what purpose they design using the process, whether for steel castings, for ingots of dead soft steel, for tool steel, or for ordnance purposes.

No. 18 Cortlandt Street, New York.

PROPULSION OF SHIPS BY AIR
Propellers.—By H. C. Vogt. Description of a novel system of marine propulsion through propellers actuated by the wind. With a detailed statement of experiments and figures of the results obtained. With two illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 670. Price 10 cents. To be had at this office and from all newsdealers.

AMATEUR PHOTOGRAPHY
EVEN THE BROWNIES MAKE PHOTOGRAPHS
WE MAKE ALL KINDS OF PHOTOGRAPHIC OUTFITS FOR AMATEURS.
Send for our New Illustrated Catalogue and copy of Modern Photography.

ROCHESTER OPTICAL CO.,
18 AQUEDUCT ST., ROCHESTER, N. Y.

BOFORS CAST STEEL GUN—BY Capt. O. E. Michaelis, U.S.A.—The production of guns from unforged open hearth steel by the casting process. The excellent quality of the guns produced, and their freedom from blow holes. A plea for cast steel ordnance. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 663. Price 10 cents. To be had at this office and from all newsdealers.

PERFECT NEWSPAPER FILE

The Koch Patent File, for preserving newspapers, Magazines, and pamphlets, has been recently improved and price reduced. Subscribers to the SCIENTIFIC AMERICAN and SCIENTIFIC AMERICAN SUPPLEMENT can be supplied for the low price of \$1.50 by mail, or \$1.25 at the office of this paper. Heavy board sides; inscription "SCIENTIFIC AMERICAN" in gilt. Necessary for every one who wishes to preserve the paper. Address **MUNN & CO., Publishers SCIENTIFIC AMERICAN.**

ROCK BREAKERS AND ORE CRUSHERS
We manufacture and supply at short notice and lowest rates, Stone and Ore Crushers, containing the invention described in Letters Patent issued to Eli W. Blake, June 15, 1886, together with NEW and VALUABLE IMPROVEMENTS, for which Letters Patent were granted May 11th and July 20th, 1880, to Mr. S. L. Marsden. All Crushers supplied by us are constructed under the superintendence of Mr. Marsden, who, for the past twenty years, has been connected with the manufacture of these Crushers in this country and England. **FABRIK FOUNDRY AND MACHINE CO.,** ANSONIA, CONN. COPELAND & BAYON, Agents, NEW YORK and PHILADELPHIA.

BIBB'S Celebrated Original BALTIMORE FIRE-PLACE HEATERS
To warm upper and lower rooms The Handsomest and Best Economical Coal-burners in the world. **B. C. BIBB & SON** Stove Foundry, Baltimore, Md. MARBLED SLATE MANTELS New and Beautiful Designs.

USEFUL BOOKS.

Manufacturers, Agriculturists, Chemists, Engineers, Mechanics, Builders, men of leisure, and professional men, of all classes, need good books in the line of their respective callings. Our post office department permits the transmission of books through the mails at very small cost. A comprehensive catalogue of useful books by different authors, on more than fifty different subjects, has recently been published for free circulation at the office of this paper. Subjects classified with names of author. Persons desiring a copy, have only to ask for it, and it will be mailed to them. Address, **MUNN & CO., 361 Broadway, New York.**

MODERN SMOKING PIPES
H. G. SCHRAMM CAMDEN, N. J.

2nd MACHINERY
N. Y. Mach'y Depot, Bridge Store 16, Frankfort St., N. Y.

INFLUENCE MACHINES.—A PAPER by James Wimshurst, giving a complete account of the recent forms of generators of static electricity. With 13 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 647. Price 10 cents. To be had at this office and from all newsdealers.

THE PENNA. DIAMOND DRILL & MFG. CO.
HARDSBORO, PA., Builders of High Class Steam Engines, Diamond Drilling and General Machinery. Flour Mill Rolls Ground and Grooved.

AGENTS \$75 per month and expenses
WANTED to sell our goods by sample and live at home. Salary paid promptly and expenses in advance. Full particulars and sample case FREE. Women just what was wanted. Address **Standard Silver-SALARY. Ware Co., Boston, Mass.**

The Paris Exposition--Illustrated.

The SCIENTIFIC AMERICAN SUPPLEMENT will for some months to come contain illustrations of the buildings and the most interesting objects to be seen at the great French Exposition opened at Paris 14 days ago. The illustrations which will embellish the SCIENTIFIC AMERICAN SUPPLEMENT will add an interesting and useful feature to the publication, and subscribers to the regular edition of the SCIENTIFIC AMERICAN, who are not patrons of the SCIENTIFIC AMERICAN SUPPLEMENT, are advised to have their name enrolled on the SUPPLEMENT subscription list at once, so as to secure all the illustrated exhibition numbers for preservation. Price, \$5 a year, \$2.50 for six months. News agents everywhere receive subscriptions, or remit to the publishers, **MUNN & CO., 361 Broadway, New York.**

BARREL, KEQ, Hogshead, AND STAVE MACHINERY.
Over 50 varieties manufactured by **E. & B. Holmes, BUFFALO, N. Y.**

PAINT YOUR ROOFS

With Dixon's Silica-Graphite Paint. It will cover two or three times more surface and last four or five times longer than any other paint. Not affected by heat or cold or acids. Send for circular.

JOS. DIXON CRUCIBLE CO., Jersey City, N. J.

TIGHT & SLACK BARREL MACHINERY
A SPECIALTY
JOHN GREENWOOD & CO
ROCHESTER, N. Y.

The Scientific American
PUBLICATIONS FOR 1889.


The prices of the different publications in the United States, Canada, and Mexico are as follows:

RATES BY MAIL.	
The Scientific American (weekly), one year	\$3.00
The Scientific American Supplement (weekly), one year	5.00
The Scientific American, Export Edition (monthly) one year	5.00
The Scientific American, Architects and Builders Edition (monthly), one year	2.50
COMBINED RATES.	
The Scientific American and Supplement	\$7.00
The Scientific American and Architects and Builders Edition	5.00
The Scientific American, Supplement, and Architects and Builders Edition	9.00
Proportionate Rates for Six Months.	
This includes postage, which we pay. Remit by postal or express money order, or draft to order of	
MUNN & CO., 361 Broadway, New York.	

Advertisements.

Inside Page, each insertion - - - 25 cents a line.
Back Page, each insertion - - - \$1.00 a line.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings and advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.



PENBERTHY IMPROVED AUTOMATIC INJECTOR.

Why 20,000 have been sold in two years. Because they cost less than others and do equal work. Lift 20 feet and work from head as well. Re-start themselves and require no watching. Will lift through hot pipes, work from 25 to 150 lbs. pressure. Parts removable without disconnecting, also interchangeable. Send for pamphlet. Penberthy Injector Co., Detroit, Mich.

THE PHONOGRAPH.—A DETAILED description of the new and improved form of the phonograph just brought out by Edison. With 8 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 632. Price 10 cents. To be had at this office and from all newsdealers.



Wheeling is Better than Walking.

Victor Bicycles

Are Better than Any Others.

Catalogue Free.

Overman Wheel Co., Makers,

BOSTON, MASS.

INVENTORS and others desiring new articles manufactured and introduced, address P. O. Box 86, Cleveland, O.

THE KODAK CAMERA



Makes 100 instantaneous pictures by simply pressing a button. Anybody can use it who can wind a watch. No focusing. No tripod. Rapid Rectilinear Lens. Photographs moving objects. Can be used indoors.

Division of Labor—Operator can finish his own pictures, or send them to the factory to be finished.

Morocco covered Camera, in handsome sole-leather case, loaded for 100 pictures.

For full description of "Kodak" see SCI. AM., Sept. 15, '88.

Price, \$25.00. Reloading, \$2.00.

The Eastman Dry Plate & Film Co.

Rochester, N. Y. 115 Oxford St., London.

Send for copy of Kodak Primer with Kodak Photograph.

THE ARMSTRONG MFG. CO.

BRIDGEPORT, CONN.

WATER, GAS AND STEAM FITTERS' TOOLS.




Stocks and Dies for Pipe, Bolts, and Brass Pipe, Wrenches, Pipe Vises, Pipe Cutters, etc. Catalogues sent free on application.

Shepard's New \$60 Screw-Cutting Foot Lathe

Foot and Power Lathes, Drill Presses, Scroll Saw, Attachments, Chucks, Mandrels, Twist Drills, Dogs, Calipers, etc. Lathes on trial. Lathes on payment. Send for catalogue of Outfits for Amateurs or Artisans. Address H. SHEPARD, 134 East 2d Street, Cincinnati, Ohio.

THE EIFFEL TOWER.—AN EXCELLENT engraving of the Eiffel one thousand-foot-high tower, which was opened to the public a few days ago, and which is to form a part of the French Exposition attractions, may be found, with description, in the SCIENTIFIC AMERICAN SUPPLEMENT, No. 554. To be had from newsdealers or at this office. Price 10 cents.



KEEP COOL!

CLARK'S Light-Running Ventilating FANS.

Adapted for Ventilating and Drying of every description. Catalogue free.

GEO. P. CLARK, Box 1, Windsor Locks, Conn.

GRAPHOPHONE AND PHONOGRAPH.

An interesting account of the Edison, Bell, and Taintor apparatus for the mechanical reproduction of speech, with detailed description of the same. With 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 669. Price 10 cents. To be had at this office and from all newsdealers.



PATENTS.

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine inventions, and to act as Solicitors of Patents for Inventors.

In this line of business they have had forty-two years' experience, and now have unequalled facilities for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reissues, Assignments, and Reports on Infringements of Patents. All business entrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reissues, Infringements, Assignments, Rejected Cases. Hints on the Sale of Patents, etc.

We also send, free of charge, a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.

MUNN & CO., Solicitors of Patents, 361 Broadway, New York. BRANCH OFFICES.—No. 622 and 624 F Street, Patent Building, near 7th Street, Washington, D. C.




PIPE COVERINGS

Made entirely of ASBESTOS.

Absolutely Fire Proof.

BRAIDED PACKING, MILL BOARD, SHEATHING, CEMENT, FIBRE AND SPECIALTIES. CHALMERS-SPENCER CO., FOOT E. 8TH ST., N. Y. BRANCHES: Phila, 24 Strawberry St. Chicago, 86 E. Lake St. Pittsburg, 414 Lewis Block.



What is more aggravating than leaky valves, whether in House, Office, or Factory? If you wish to avoid annoyance, INSIST on having Jenkins Bros. Valves. Accept no valves as Jenkins Bros. unless stamped with our "Trade Mark" like cut.

JENKINS BROS.

71 John Street, New York. 105 Milk Street, Boston. 21 North 5th Street, Phila. 54 Dearborn Street, Chicago.

THE ONLY PRACTICAL Low-Priced Typewriter

First-Class, Rapid, Durable, Business WORLD TYPEWRITER, 44 characters, \$10; 77 characters, \$15.


Catalogue free. Typewriter Dept., POPE MFG. CO., Boston, New York, Chicago.



POP SAFETY VALVE WATER RELIEF VALVE IMPROVED STEAM GAGE STEAM ENGINE INDICATOR

Single Bell Chime Whistle, and all instruments used in connection with Steam, Air and Water. Sole Agents for Clark's Lamin Fire Hose.

NEW YORK. LONDON. GOSBY STEAM GAGE & VALVE CO., Boston, Mass.



The CUSHMAN Patent 3 Pinion Gearing Scroll Chucks with their latest improvements are unexcelled. Made in all sizes from 2 1/2 inch to 12 inch diameter, and are sold by the trade all over the world. Manufactured by The Cushman Chuck Co., Hartford, Conn.

WORKING MODELS and Experimental or wood, made to order by MASON & RATCH, successors to J. F. Werner, 62 Centre Street, New York.



H. W. JOHNS' Asbestos PATENTED Roofing


FIRE-PROOF.

This is the perfected form of Portable Roofing manufactured by us for the past thirty years; is adapted for use on steep or flat roofs in all climates, can be easily applied by unskilled workmen, and costs only about half as much as tin. Samples and descriptive price list free by mail.

H. W. Johns Mfg. Co., 87 Malden Lane, N. Y. CHICAGO. PHILADELPHIA. LONDON.

SOLE MANUFACTURERS OF

H. W. Johns' Liquid Paints, Asbestos Fire-Proof Paints, Sheathings, Building Felts, Asbestos Steam Packings, Boiler Coverings, etc. VULCABESTON Moulded Piston-rod Packing Rings, Gaskets, etc.



OTTO GAS ENGINES.


Over 25,000 Sold.

Horizontal.....Otto...Gas Engines.
Vertical.....Otto...Gas Engines.
Twin Cylinder.....Otto...Gas Engines.
Combined.....Otto...Gas Engines and Pumps.
Combined.....Otto...Gas Engines and Dynamos.

OTTO GAS ENGINE WORKS, CHICAGO, PHILADELPHIA.

New York Agency, 15 Vesey Street.

PULLEYS. Cheapest, Lightest, and Best. Made by Hardwood Split P. Co., Menasha, Wis.



VAN DUZEN GAS ENGINE

NO BOILER. NO COAL. NO ENGINEER.

No Extra WATER RENT or INSURANCE.

INSTANTLY STARTED.

DURABLE, RELIABLE, SAFE and ECONOMICAL.

Send for description and prices.

Van Duzen Gas Engine Co., 68 E. 2nd St., CINCINNATI, O.

THE AMERICAN BELL TELEPHONE CO.

95 MILK ST., BOSTON, MASS.


This Company owns the Letters Patent granted to Alexander Graham Bell, March 7th, 1876, No. 174,465, and January 30th, 1877, No. 186,787.

The transmission of Speech by all known forms of Electric Speaking Telephones infringes the right secured to this Company by the above patents, and renders each individual user of telephones not furnished by it or its licensees responsible for such unlawful use, and all the consequences thereof, and liable to suit therefor.



CUTLER DESK.

BEST IN THE WORLD. A. CUTLER & SON, BUFFALO, N. Y., U. S. A.



THE COPYING PAD.—HOW TO MAKE and how to use; with an engraving. Practical directions how to prepare the gelatine pad, and also the aniline ink by which the copies are made; how to apply the written letter to the pad; how to take off copies of the letter. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 438. Price 10 cents. For sale at this office and by all newsdealers in all parts of the country.




BARBLESS HOOKS. All sizes, No. 1 to 10. Made of best wire. No spitting out. No trouble landing every bit. 7 samples, 25c. No. 5, 30c. per doz., postpaid. Best English Spring Steel Bass Hooks, 10c. a doz. **SPOON HOOKS** for pike or bass, 15c.; rubber minnows, 50c.; trout flies, 15c. doz. best; 75 ft. braided linen line, 25c. postpaid. Chinese grass line, 20 ft., 25c. 75 ft. reel, 35c. postpaid. Free list of Cutlery and Fishing Tackle. **MAHER & GROSH, 40 S. St., Toledo, Ohio.**

PATENT JACKET KETTLES, Plain or Porcelain Lined. Tested to 100 lb. pressure. Send for Lists. **BLAND, BURR & CO., 614 and 616 Market St., Philadelphia, Pa.**



JUST OUT! ALUMINUM-STEEL HACK SAW. Frame and 1 doz. blades, \$2; Blades per doz., 8-inch, \$1. by mail upon receipt of price. Hard but not brittle. **CRESCENT MFG. CO., CLEVELAND, O.** New catalogue of Engineers' Specialties.



COMPLETE STEAM PUMP ONLY SEVEN DOLLARS DEMAND THIS PUMP OF YOUR DEALER OR WRITE TO US FOR PRICES. **VAN DUZEN'S PATENT VAN DUZEN & TIFT, SOLE MAKERS CINCINNATI, O.**

HOME-MADE INCUBATOR.—PRACTICAL directions for the manufacture of an effective incubator that has been carefully tested and found to perform all that may be reasonably expected; with directions for operating. With 4 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 630. Price 10 cents. To be had at this office and from all newsdealers.

ANNOUNCEMENT! Improved methods and special tools make it possible for us to manufacture Elevators, to be operated from line of shafting, at a largely reduced cost. Purchasers desiring a safe and reliable Elevator, which has stood the test of 37 years' use, should apply to us for an estimate. All our Elevator machinery is made of the very best materials, and by skilled workmen. Also manufacturers of Hydraulic Passenger and Freight Elevators. **OTIS BROTHERS & CO., 38 Park Row, New York.**



TIMBER AND SOME OF ITS DISEASES—An elaborate and a very valuable series of papers showing the various causes of the decay of timber and how in many cases it can be prevented. Illustrated with 39 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 637, 638, 640, 643, 644, 648, 656, 661, 664, 665. Price 10 cents each, or \$1 for the entire series. To be had at this office and from all newsdealers.

SYRACUSE MALLEABLE IRON WORKS

W B BURNS PROP^{TY}

TO BUSINESS MEN.

The value of the SCIENTIFIC AMERICAN as an advertising medium cannot be overestimated. Its circulation is many times greater than that of any similar journal now published. It goes into all the States and Territories, and is read in all the principal libraries and reading rooms of the world. A business man wants something more than to see his advertisement in a printed newspaper. He wants circulation. This he has when he advertises in the SCIENTIFIC AMERICAN. And do not let the advertising agent influence you to substitute some other paper for the SCIENTIFIC AMERICAN, when selecting a list of publications in which you decide it is for your interest to advertise. This is frequently done, for the reason that the agent gets a larger commission from the papers having a small circulation than is allowed on the SCIENTIFIC AMERICAN. For rates see top of first column of this page, or address

MUNN & CO., Publishers, 361 Broadway, New York.

Novelty HOT AIR Furnaces

Expose an Immense Heated Surface. Extract all the Heat from the Gases, Furnish Pure Warm Air in abundance. Fifteen Years of Test. Universally Satisfactory. Send for "Our Furnace Book."

Abram Cox Stove Co., MANUFACTURERS, Philadelphia and New York.

KEY SEATING Machines and 20" Drills. W. P. DAVIS, Rochester, N. Y.

THE Scientific American

ESTABLISHED 1846.

The Most Popular Scientific Paper in the World.

Only \$3.00 a Year, including Postage. Weekly. 52 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc. Complete List of Patents each week.

Terms of Subscription.—One copy of the SCIENTIFIC AMERICAN will be sent for one year—52 numbers—postage prepaid, to any subscriber in the United States or Canada, on receipt of three dollars by the publishers; six months, \$1.50; three months, \$1.00.

Clubs.—Special rates for several names, and to Post Masters. Write for particulars.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

MUNN & CO., 361 Broadway, New York.

THE Scientific American Supplement.

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages full of engravings, many of which are taken from foreign papers, and accompanied with translated descriptions. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archaeology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information obtainable in no other publication.

The most important Engineering Works, Mechanisms, and Manufactures at home and abroad are illustrated and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, \$5.00 a year, or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for \$7.00. Single copies 10 cents. Address and remit by postal order, express money order, or check.

MUNN & CO., 361 Broadway, N. Y., Publishers SCIENTIFIC AMERICAN.

Building Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS' AND BUILDERS' EDITION is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming a large and splendid Magazine of Architecture, richly adorned with elegant plates in colors, and with other fine engravings; illustrating the most interesting examples of modern Architectural Construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country, including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with full Plans, Specifications, Sheets of Details, Estimates, etc.

The elegance and cheapness of this magnificent work have won for it the Largest Circulation of any Architectural publication in the world. Sold by all newsdealers. \$2.50 a year. Remit to

MUNN & CO., Publishers, 361 Broadway, New York.

PRINTING INKS.

THE "Scientific American" is printed with CHAS. E. JOHNSON & CO.'S INK. Tenth and Lombard Sts., Phila., and 47 Rose St., opp. Duane St., N. Y.